

MAY 16 1997

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY (County)
HILLMAN TWP.

Located In:

Corner Code #

- 1. Public Land Survey T 31N R 4E B - 13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-01-1996 09:41:32

A. PANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13 containing numbers 1-36.

I, DONALD E. MARLATT, in a field survey on 7-1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13 SOUTH 1/4 COR. SEC. 31
COR. SET BY LEWIS CLASON 3-18-1839
W. PINE 12"-N18°W-21', W. PINE 18"-N51°W-17'.
ACT 74 BY KEN OSTLING L. 1, P. 326, 8-17-1982. SET DNR MONUMENT BY S.P. METHOD.
N10°E 6"MAPLE 3.4' - S78°E 5"MAPLE 11.9'
DNR SURVEY 1982. SURVEY REPORT ON FILE.

NOTE: M.S.H.D. SURVEY DATED 4-5-1966 WAS NOT ACCEPTED FOR CORNER POSITION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B - 13 SOUTH 1/4 COR. OF SEC. 31
FOUND DNR MONUMENT
N10°E 3.5' 9"MAPLE, S78°E 11.95' 7"MAPLE

APPROVED BY PEER GROUP

JUL 12 1996


[Signature]

NORTH CORNER COMMON TO SEC'S 5 & 6, T30N, R4E IS 90.45' WEST
NO EVIDENCE OF ORIGINAL CORNER

NOTE: MSHD SURVEY DATED 4-5-1966 WAS NOT ACCEPTED FOR CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B - 13 SOUTH 1/4 COR. OF SEC. 31, T31N, R4E.
LEFT DNR MONUMENT IN PLACE (1"PIPE WITH 4"CAP)
N10°E 3.5' 9"MAPLE
S78°E 11.95' 7"MAPLE
S 7°E 22.23' 12"OAK
N58°W 8"MAPLE 28.4'



WITNESSES MARKED WITH 30 PENNY SPIKES AND P.S. TAGS #18660.
APPROVED BY PEER GROUP JULY 12, 1996 AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Donald E. Marlatt

Date 10/28/96

Surveyor's Michigan License No. 18660