

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION MONTMORENCY (County)

Located in: HILLMAN TWP Corner Code #

- 1. Public Land Survey T 31N R 4E D-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

APPROVED BY PEER GROUP

AUG 05 94

[Signature]

STATE OF MICHIGAN MONTMORENCY COUNTY Recorded & Filed

10-19-1994 13:48:49

REGISTER OF DEEDS

- 4. Lot No. Recorded Plat
5. Private Claims

I, FREDERICK J. KING, in a field survey on July 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1 NORTH 1/4 CORNER SECTION 5

July 1855 - Original Post set by Butler Ives, D.S.

S57E - Cedar - 5.94' (9 lks)

N47W - Tamarack - 11.88' (18 lks)

May 1947 - 4" Pipe & Cap set by Shadko - No Witnesses Shown

Does not indicate method used to set corner or any evidence fnd.

July 1983 - Act #74 Rec Bk 1, Pg 345 by R.R. Bisher, PS # 22428

N68E - 4.44' 8" Cedar

Fnd DNR Mon by G.A. Shadko, stamped "1947"

S17E - 11.14' - 4" Cedar

S60W - 3.63' - 16" Cedar (Old Wit)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 NORTH 1/4 CORNER SECTION 5

7-29-94 - Fnd Rec 4" Pipe with DNR Cap MKd set by G.A. Shadko - 1947

N55E (R-N68E) - 4.49' (R-4.44') Tag #15410 in Cedar

S17E - 11.43' (R-11.14') - Tag #22428 in Cedar

S45W - (R-S60W) - 3.56' (R-3.63') - Tag #15410 in Cedar

N15W - 18.02' - Tag #22428 in Cedar

West - 72.4' (R-72.6') - Fnd 4" Pipe with DNR Cap Mkd set by G.A. Shadko in 1947 +/- 37' E of E Shore of Long Lake.

No 1855 Wit fnd.

This Corner Approved by County Peer Review on Aug. 5, 1994 as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 NORTH 1/4 CORNER SECTION 5

7-29-94 - Fnd 4" Pipe & Cap set by Shadko in 1947

N55°E - 4.49' - Set Tag above Tag #15410 in SE Sd 6" Cedar

S20°E - 11.43' - Set Tag Above Tag #22428 in E Sd 6" Cedar

S45W - 3.56' - Set Tag above Tag #15410 in NW Sd 18" Cedar

N15W - 18.02 - Set Tag above #22428 in W Sd 6" Cedar

West - 72.4' - 4" Pipe & Cap by Shadko

Existing Red Top Post alongside Corner



Signed by Frederick J. King

Date 10-18-94

Surveyor's Michigan License No. 25852