

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION (County)

Located In: HILLMAN TWP.

Corner Code # F-1

STATE OF MICHIGAN MONTMORENCY COUNTY Recorded & Filed

10-19-1994 13:49:23

A. PANGAN-MCELROY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 31N R 4E F-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

APPROVED BY PEER GROUP

AUG 05 94

[Signature]

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column F and row 2.

I, FREDERICK J. KING, in a field survey on July 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1 NORTH 1/4 CORNER, SECTION 4

- July 1855 - Original Post set by Butler Ives, D.S. S55E - Dead Y Pine - 14.52' (22 lks) N06E - Dead Y Pine 15.18' (23 lks)
July 1933 - 1/2"x30" Bar Set by Delamater - Per Shadko Notes - No Witnesses
Dec. 1953 - Fnd Delamater 1/2" Iron - Replaced with 4" Pipe & Cap Set by Shadko- Notes state both Gvmt B.T.'s Fnd S150E - 41.6' - 4" R.Oak - S580W - 64.4' - 18" Y. Pine Stump
Dec. 1973 - Act #74 Rec Bk 1, Pg 81 by D.E. Porter, PS#15410 - Fnd Bt Spk & Old Wit Stmp - S58W -64.60'- 18" Pir Stump. - S15E - 41.91' - 9" Oak - N15E - 82.30' - 16" Oak
1975 - Field Notes obtained from L.G. Beauregard - Fnd Boat Spk. S15E - 41.50' - 10" Oak -- S40W -57.90' 15" Oak -- South - 23.56' - Conc Mon.
Apr 1979 - Act #132 Rec L 2, Sur, Pg. 516. by D.E. Porter, PS#15410 - Fnd DNR Mon -- SAME WITNESSES AS 1973
Apr. 1979 - Act #74 Rec Bk 1, Pg 259 by R.R. Bfsher, PS#22428 - Fnd DNR Mon -- SAME WITNESSES AS 1973
Aug. 1980 - Act #132 Rec L23, Pg. 55 by L.G. Beauregard, PS #18654 - Fnd DNR Mon -- SAME WITNESSES AS 1973

B2 Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 NORTH 1/4 CORNER, SECTION 4

7-26-94 - Fnd Rec DNR Mon., Broken and Tipped approx. 45° West with Cap bent approx. 90° approx 3ft deep, inside what appears to be a piece of 8" Stove Pipe.

Left Fnd Mon in Place, but Set 1/2" Iron & Mont Co Re-Mon Cap, as follows:

Fnd 1/2" Iron & Porter Cap on N ROW Line of Rd & West of Cor F-1 on Sec line as Rec in L 2, Pg 516. Meas 57.22' S of Iron on N Row AND Meas 231.87' E of Iron on Sec Line, as Recorded. Set Iron & Re-Mon Cap @ Intersection Point, Agrees Well with Rec Witnesses Fnd: N150E - 82.2' (R-82.30) - Fnd Blz in Rec Oak S150E - 41.8' (R-41.91) - Fnd Blz in Rec Oak South - 23.56' - Fnd Rec Conc. Mon.

This corner approved by County Peer Review on Aug. 5, 1994 as the best available evidence of the Re-Establishment of Original Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-1 Set 1/2" Re-Rod & Co Re-Mon Cap 7-26-94 ± 24' S of C.L., E-W B.T. Road (Co Rd. # 451) North - 57.22'- Iron & ID Cap #15410 N150E - 82.20' - Set Tag E Side 20" Oak S150E - 41.88' - Set Tag E sd 12" Oak South - 23,56' - Conc Mon S600W - 29.11' - Set Tag SE sd 10" Oak West - 231.87' - Iron & ID Tag #15410 Set Treated 2"x4" Along side.



Signed by Frederick J. King

Date 10-18-94

Surveyor's Michigan License No. 25852