

SURVEY & REMONUMENTATION

Montmorency County Remonumentation

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 MONTMORENCY COUNTY
 Recorded & Filed

10-19-1994 13:49:53

A. PANGAN-MCELROY
 REGISTER OF DEEDS

Liber 00012 Page 0076

Register of Deeds Stamp & File Number

For corners in
COMMISSION
 MONTMORENCY
 (County)

Located In: Corner Code #
 HILLMAN TWP. G-1

- 1. Public Land Survey T 31N R 4E G-1
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

**APPROVED BY
 PEER GROUP**

AUG 0 5 94

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

I, FREDERICK J. KING, in a field survey on July 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-1 **CORNER COMMON TO SECTIONS 3 & 4**
 - July 1855 - Original Post set by Butler Ives, D.S. N86W - Y Pine - 26.40' (40 lks) N46E - Dead W Pine - 33.66' (10 lks)
 - July 1933 - 1/2"x30" Bar Set by Delamater - per Shadko notes - Method used not indicated - NO WITNESSES SHOWN
 - Dec 1953 - Fnd Delamater Iron - Replaced by Shadko with 4" Pipe & DNR Cap. - States all 4 Gvmt B.T.s Found
 - N50W - 97.7 - 12" W.Pine -- N570E - 64.0' - 8" Y Pine
 - UnDated - Field Notes by un-known obtained from L.G. Beauregard PS#18654 - Fnd 1/2" Bar and all 4 Gvmt BTs & Delmater Post -- N05W - 12" W Pine - 97.7' -- N57E - 8" Y Pine - 64.0'
 - Aug 1966 - Un-Recorded Sur by un-known Surveyor, Obtained from L.G. Beauregard PS#18654 - NO WITNESSES SHOWN
 - Breakdown of Entire Sec.4
 - Aug 1971 - Act 132 Rec L 1, Pg 74 by G.G. Slattery -- SAME WITNESSES AS ABOVE
 - Aug 1980 - Act 132 Rec L 3, Pg 55 by L.G. Beauregard, PS #18654 - Fnd DNR Mon -- N01W - 20" W Pine - 98.2'
 - N61E - 16" Norway - 64.70'
 - S25E - 10" Oak -- 22.28'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-1 **CORNER COMMON TO SECTIONS 3 & 4**
 - 7-28-94 - Fnd Rec DNR 4" Pipe & Cap - North - 97.6' (R-97.7' & 98.2') - Fnd Blz in W Pine
 - 1953 - mkd set by G.A. Shadko in. N600E - 64.7' (R-64.7' & 64.0') - Fnd Blz in Norway
 - No 1855 Wit Fnd.

This Corner Approved by County Peer Review on Aug 5, 1994 as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-1 **CORNER COMMON TO SECTIONS 3 & 4** 7-28-94
 - Fnd 4" Pipe & Shadko Cap
 - North - 97.6' - Set Tag W sd 27" W Pine
 - N550E - 7.23' - Set Tag SE sd 12" Oak
 - N600E - 64.72' - Set Tag NW sd 24" Norway
 - S250E - 22.3' - fnd Blaze in Rec Oak (Now Stump)
 - N450W - 15.02' - Set Tag NE side - 12" Oak
 - Set Treated 2"x4" Along side



Signed by Frederick J. King Date 10-18-94
 Surveyor's Michigan License No. 25852