

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00012 Page 0149

For corners in

Montmorency (County) Located In: Hillman Township Corner Code # G-13

1. Public Land Survey T 31 N R 4 E
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 MONTMORENCY COUNTY
 Recorded & Filed

09-22-1995 11:30:25

A. PANGAN-MCELROY
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

APPROVED BY PEER GROUP

JUN 2 95

G.B.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Larry G. Beauregard, in a field survey on May 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

4-18-1840, Lewis Clason, Deputy Surveyor, set corner, Sections 33 and 34. Witnesses marked: (N 54° W 25 links 8" Hemlock (N 59° E 32 links 10" Hemlock).

2-1972, Ronald Bischer, P.S. #22428, PORTER'S SURVEY, Found and accepted 3/4" pipe in Road centerline for corner. Witnesses marked: (North 28.15' Corner fence post) (S 65° W 74.39' Corner fence post) (S 40° W 67.70' P. Pole).

10-1981, Delmer E. Porter, P.S. #15410, Found 3/4" pipe at the Southeast corner of Section 33. Witnesses marked: (North 28.15' Fence corner) (S 40° W 67.70' P. Pole) (S 65° W 74.39' Fence corner). Certificate of Survey, Recorded L. 3, P. 151, Montmorency County Records.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 12" pipe of record in centerline of road in line with fence line North and witnesses mentioned above from Porter's survey.

SURVEY & REMONUMENTATION

DEC 1 8 1995

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner common to Sections 33 and 34, T 31 N, R 4 E

Placed 4" diam., x 36" standard concrete monument with a Montmorency County Remonumentation Cap P.S. #18654. Accepted as the best available evidence of the position of the original corner. Approved by the Peer Group on June 2, 1995.

- N 18° W 81.85' 9" Norway
- N 45° W 73.03' 9" Norway
- N 40° W 39.89' Corner fence post (P.K. nail & P.S. tag #18654)
- S 30° W 67.00' Power Pole (R) (P.K. nail & P.S. tag #18654)
- West 65.40' N. 1/4 corner of Sec. 3, T 30 N, R 4 E

Placed 60d spike & P.S. tag #18654 (typ)

Signed by Larry G. Beauregard Date 9/22/95
 Surveyor's Michigan License No. 18654