

DEC 18 1995

Liber 00001 Page 0526

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00012 Page 0150

For corners in

Montmorency (County)	Located In:	Corner Code #
	Hillman Township	
1. Public Land Survey	T 31 N R 4 E	H-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

09-22-1995 11:30:41

A. PANGAN-MCELROY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Larry G. Beauregard, in a field survey on June 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

4-18-1840, Lewis Clason, Deputy Surveyor, Set 1/4 Section post. Witnesses marked: (N 58° W 47 links 10" Beech) (N 58° E 21 links 10" Beech).

7-1930, G.F. DeLaMater, P.S. #693, Found 2" pipe at corner. Witnesses marked: (S 65° E 42.5' 14" Elm) (S 59° W 33.0' 8" Elm).

7-1985, Donald E. Marlatt, P.S. #18660, Found 2" pipe at corner, 68.85' East of closing corner for Sections 2 & 3, T 30 N, R 4 E. No witnesses marked.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" x 12" pipe 68.86' East of closing corner for Sections 2 & 3, T 30 N, R 4 E, 2' below road surface.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South 1/4 corner of Section 34, T 31 N, R 4 E

Placed 4" diam., x 36" concrete monument and Montmorency County Remonumentation Cap P.S. #18654. Accepted as the best available evidence of the re-establishment of the original corner. Approved by the Peer Group on June 2, 1995.

- S 75° W 105.55' 36" Elm (R) (Placed 60d spike, blaze and P.S. tag #18654)
- S 25° W 95.42' Power Pole (Placed P.K. nail and P.S. tag #18654)
- S 50° W 142.43' 4" Elm (Placed 60d spike, and P.S. tag #18654)
- S 55° W 31.78' Corner fence post (Placed P.K. nail and P.S. tag #18654)
- West 68.68' Closing corner Sec. 2 & 3, T 30 N, R 4 E
- West 37.0'± Centerline of existing Road, North & South

APPROVED BY  
PEER GROUP

JUN 02 95 A.B.

Signed by Larry G. Beauregard Date 9/22/95  
Surveyor's Michigan License No. 18654