

SURVEY & REMONUMENTATION Montmorency County Remonumentation

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY COMMISSION
(County)

Located In: HILLMAN TWP. Corner Code #

Liber 00012 Page 0078

- 1. Public Land Survey T 31N R 4E I-1
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

APPROVED BY PEER GROUP

AUG 05 94

[Signature]

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

Register of Deeds Stamp & File Number

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

A. PANGAN-MCELROY
REGISTER OF DEEDS

	G	H	J	K	L	M
2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

I, FREDERICK J. KING, in a field survey on July 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1 CORNER COMMON TO SECTIONS 2 & 3

July 1855 - Original Post set by Butler Ives, D.S.

N87E - W Pine - 38.28' (58 lks)
N15W - Elm - 9.90' (15 lks)

Mar: 1973 - Act #74 Rec Bk 1, Pg 60 by D.E. Porter
PS # 15410 - Fnd 1/2", #12018 in Mon Box

N25E - Pwr Pole - 84.14'
S50W - 12" Cedar - 43.90'

July 1981 - Act 132 Rec L 3, Sur, Pg 103 by D.E. Porter, PS #15410 - Fnd 1/2" Rod & Cap

SAME WITNESSES AS ACT # 74 ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 CORNER COMMON TO SECTIONS 2 & 3

7-26-94 - Fnd Rec 1/2" Iron & Cap #12018
in Mon Box

N25°E - 84.00' (R-84.14') - Fnd Tag #15410 in Pole #AV1-32E-13

Area to SW has been cleared - Rec Cedar BT Gone

This Corner Approved by County Peer Review on Aug. 5, 1994, as the best available evidence of the re-establishment of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 CORNER COMMON TO SECTIONS 2 & 3

7-26-94 Placed Co Re-Mon Cap on Fnd 1/2" Iron in Mon Box
Cor is 15' S of C.L. of E-W Rd. (Anchor Lake Rd) &
in C.L. of B.T. Rd to N. (Morrow Rd)
N25°E - 84.00' - Set Tag in Pole #AV1-32E-13, above Tag Fnd
S80°E - 102.37' - W Face of "Pass With Care" sign Post
South - 10.5' - Set Treated 2"x4"
S70°W - 30.25' - NE Cor of "Stop" Sign Post
N60°W - 57.86' - NE Cor of "Buried Cable" sign post



Signed by Frederick J. King Date 10-18-94

Surveyor's Michigan License No. 25852