

SURVEY & REMONUMENTATION

Montmorency County Remonumentation Liber 00012 Page 0081

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corner **COMMISSION**
MONTMORENCY
(County)

Located In: **HILLMAN TWP.** Corner Code ##

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

- 1. Public Land Survey T 31N R 4E 1-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____ **AUG 0 5 94**
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

10-19-1994 13:51:29

A. PANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, **FREDERICK J. KING**, in a field survey on **July 25**, 19 **94**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-1 **NORTH 1/4 CORNER, SECTION 1.** July 1855 - Original Post set by Butler Ives, D.S. N41W - Dead Hem.-8.58' (13 1 S57E - Dead Hem.-9.24' (14 1
Oct. 1973 - Act #74 Rec Bk 1, Pg 70 by D.E. Porter, PS#15410 - Fnd 1/2" Iron & Cap #18654
N50°E - Fnc Cor Post - 42.77' -- N45W - 20" Apple - 81.97' -- S05E - Pwr Pole - 38.64'
Un-Dated - Un-Recorded Field Notes, obtained from L.G. Beauregard, PS #18654 - Fnd 1/2" Rod -- S03E - Pwr Pole - 38.51' -- N30W - 18" Apple - 81.54'.
June 1974 - Act #132 Rec L 1, Pg 478 by D.E. Porter, PS #15410 - Fnd 1/2" Rod & Cap - SAME WITNESSES AS ACT #74 SH
Oct. 1978 - Act #132 Rec L 2, Pg 492 by D.E. Porter, PS #15410 - Fnd 1/2" Rod & Cap - SAME WITNESSES AS ACT #74 SH
Oct. 1989 - Act #132 Rec 3, Pg 518 by E.T. Lewis, PS #27452 - Fnd 1/2" Iron - SAME WITNESSES AS ACT #74 SHOWN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-1 **NORTH 1/4 CORNER, SECTION 1**
7-25-94 Fnd Rec 1/2" Iron & Cap #18654 N40°W (R-N45W & N30W) - 82.12' (R-81.97' & 81.54')
Fnd Rec Apple BT
S05°E - 38.68' (R-38.64' & 38.51') - Fnd Tag 15410
In Pole #AV1-32G-2
No 1855 Wit Fnd.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-1 **NORTH 1/4 CORNER, SECTION 1**
7-25-94 Placed Co Re-Mon Cap on Fnd 1/2" Iron
Cor is in Line with Existing Fnc to South & is in C.L. of E-W Gravel Rd (Long Rapids Rd) & on W edge of 2- Track to North & ± 36' E of edge of Drive to Hse # 148
N20°E - 36.45' - Set Treated 2"x4"
S05°E - 38.68' - Set Tag above Fnd Tag in Pwr Pole # AV1-32G-2
N50°W - 42.03' - SE Cor Phone Box
N40°W - 82.12' - Set Tag NE side 24" Apple

Signed by *Frederick J. King*

Date 10-18-94

Surveyor's Michigan License No. 25852

