

For corners in

Montmorency
 (County)

Located In: Hillman Township Corner Code M-13

1. Public Land Survey T 31 N R 4 E _____ M-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

STATE OF MICHIGAN
 MONTMORENCY COUNTY
 Recorded & Filed

09-22-1995 11:32:01

A. PANGAN-MCELROY
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

**APPROVED BY
 PEER GROUP**

UN 0 2 95

A-B

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

I, Larry G. Beauregard, in a field survey on May 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

4-18-1840, Lewis Clason, Deputy Surveyor, Set post, T 31 N, R 4 E & 5 E. Witnesses marked: (N 62° W 24 links 14" Y. Birch) (N 77° E 50 links 15" B. Ash).

3-1902, William H. LeRoy, Alpena County Surveyor, Found and or re-set corner from GLO notes. No new witnesses marked.

1986, Jim Schwandt, P.S. #26466, Granger Engineering, Inc. Found 4.5" square Cedar post 2.2' above ground. Found evidence of Ash stump, 16" diam., N 77° E 50 links. Also found evidence of Birch stump, 14" diam., N 62° W 24 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Existing 4" x 36" concrete monument 1'± above ground with no I.D. cap. Also 4½" square cedar stake along side by LeRoy (Alpena Co. Surveyor about 1902. NOTE: It is not known who set the concrete monument.

**SURVEY &
 REMONUMENTATION**

DEC 1 8 1995

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Southeast corner of Section 36.

4" diam., x 36" standard concrete monument, placed a Montmorency County Remonumentation Cap P.S. #18654 on same. Accepted as a perpetuation of the original Government corner. Approved by the Peer Group on June 2, 1995.

- S 30° W 10.50' 11" Maple
- S 55° W 37.23' 16" Maple
- N 80° W 20.59' 10" Ash
- N 05° E 40.61' 5" Ash

Placed blaze, 60d penny spike and P.S. tag #18654 (typ). North & South fence line 7.5'± West of monument.

Signed by Larry G. Beauregard

Date 9/22/95

Surveyor's Michigan License No. 18654