

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

08133

A. PANGAN-NEELROY

Asst. Reg. Surveyor

DEC 20 10 12 AM '93

RECEIVED
MONTMORENCY COUNTY
REGISTERED DEEDS

RECEIVED

For corners in

Montmorency
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 32N R 1E

A-1

T 32N R 1E

A-2 ✓

T _____ R _____

T _____ R _____

**APPROVED BY
PEER GROUP**

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

NOV 0 5 93

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Donald E. Marlatt, in a field survey on DEC 10, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-1) Post Cor. set by Austin Burt 1850.
Pine 24-N 26 E-21
Hemlock 14-S 37 W-32
Land Corner Record by Ken Ostling
Nov. 1, 1962.
Act 74 by Czubak L. 2, P. 200.

(A-2) W. 1/4 Cor. Sec. 6, T32N, R1E
Post set by Austin Burt 1850.
Sugar 16-N 22 E-11
Hemlock 16-S 64 W-25
1928 G.F. De La Mater Est. midway
in line.
Cedar stp. West 11.0'
Cedar stp. side 5.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-1) N.W. Cor. Sec. 6, T32N, R1E
Fnd. DNR Mon.
N 50° E 24" N. Pine 67.35' Ex.
N 43° W 10" Spruce 27.95' Ex.

(A-2) W. 1/4 Cor. Sec. 6, T32N, R1E
Fnd. no evidence of corner.
Set 1/2" x 24" rod & Re-Mon. cap
midpoint & on line between
N.W. & S.W. Cors. of Sec. 6.

No evidence of original corner.

The Peer Group approved (A-1) as a perpetuation of the original government corner.
The Peer Group approved (A-2) as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-1) N.W. Cor. Sec. 6, T32N, R1E
Fnd. DNR Mon.
N 50° E 24" N. Pine 67.35'
N 43° W 10" Spruce 27.95'
S 78° W 14" Spruce 20.62'
S 48° W 10" Spruce 46.56'

(A-2) 1/2" X 24" ROD & REMON. CAP
W. 1/4 Cor. Sec. 6, T32N, R1E
N 53° E 7" Maple 16.17'
S 33° E 9" Maple 11.04'
S 54° W 11" Maple 13.12'
N 28° W 10" Maple 8.38'

Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt

Date Dec 15, 1993

Surveyor's Michigan License No. 18660

