

Montmorency County Re-monumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

08134
RECEIVED
MONTMORENCY CITY
REGISTER OF DEEDS
DEC 20 10 12 AM '93
A. PANGAN-MCELROY

For corners in Montmorency (County) Located In: _____ Corner Code ##

1. Public Land Survey T 32N R 1E A-3 ✓
T 32N R 1E A-4
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

APPROVED BY
PEER GROUP

NOV 05 93

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Donald E. Marlatt, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-3) S.W. Cor. Sec. 6, T32N, R1E
Post Cor. set by Austin Burt 1850.
Hemlock 8-S 23 W-26
Hemlock 8-N 45 E-7
Hemlock 8-N 50 E-6
B. Ash 8-S 73 E-15
Act 74 by J. Wilcox L. 1, P. 277.
Act 74 by L. Czubak L. 2, P. 200.

(A-4) W. 1/4 Cor. Sec. 7, T32N, R1E
Post Cor. set by Austin Burt 1850.
Cedar 14-S 37 E-14
Balsam 10-N 51 W-30
Survey by Duane MacNeill for
Steve Fletcher 8-18-1988.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-3) S.W. Cor. Sec. 6, T32N, R1E
Fnd. 1/2" rod & sq. stake.
N 20° W 8" Balsam 7.62' Ex.
S 28° E 9" Maple 19.25' Ex.
30' East of Trail.

(A-4) W. 1/4 Cor. Sec. 7, T32N, R1E
Fnd. 1" bar
S 20° E 16" Cedar 17.82' Ex.
N 85° W 13" Cedar 17.10' Ex.
N 5° W 12" Cedar 29.35' Ex.

No evidence of original corner.

No evidence of original corner.

The Peer Group approved (A-3) & (A-4) as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-3) S.W. Cor. Sec. 6, T32N, R1E
Placed Mont. Re-Mon. cap on 1/2" rod.
N 20° W 8" Balsam 7.62'
S 25° W 11" Maple 9.16'
S 28° E 9" Maple 19.25'
N 50° E 8" Maple 14.45'

(A-4) W. 1/4 Cor. Sec. 7, T32N, R1E
1" bar
S 20° E 16" Cedar 17.82'
N 85° W 13" Cedar 17.10'
N 5° W 12" Cedar 29.35'
S 85° E 8" Cedar 11.60'

Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt

Date Dec 15, 1993

Surveyor's Michigan License No. 18660

