

### Montmorency County Remonumentation

#### LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

or corners in

Montmorency (County)	Located In:	Corner Code ##
Public Land Survey	T 32N R 1E	A-3
	T 32N R 1E	A-4 ✓
	T _____ R _____	
	T _____ R _____	
Property Controlling in Section	S _____ T _____ R _____	<b>APPROVED BY PEER GROUP</b>
Miscellaneous Property in Sec.	S _____ T _____ R _____	
		NOV 05 93

08124  
 RECEIVED  
 MONTMORENCY CITY  
 REGISTER OF DEEDS  
 DEC 20 10 12 AM '93  
 A. PANGAN-MCELROY

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3	7	8	9	10	11	12						
4												
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Donald E. Marlatt, in a field survey on December 10, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- |   |  |
|---|--|
| <p>A-3) S.W. Cor. Sec. 6, T32N, R1E<br/>         Post Cor. set by Austin Burt 1850.<br/>         Hemlock 8-S 23 W-26<br/>         Hemlock 8-N 45 E-7<br/>         Hemlock 8-N 50 E-6<br/>         B. Ash 8-S 73 E-15<br/>         Act. 74 by J. Wilcox L. 1, P. 277.<br/>         Act 74 by L. Czubak L. 2, P. 200.</p> | <p>(A-4) W. ¼ Cor. Sec. 7, T32N, R1E<br/>         Post Cor. set by Austin Burt 1850.<br/>         Cedar 14-S 37 E-14<br/>         Balsam 10-N 51 W-30<br/>         Survey by Duane MacNeill for<br/>         Steve Fletcher 8-18-1988.</p> |
|---|--|

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- |   |  |
|---|--|
| <p>A-3) S.W. Cor. Sec. 6, T32N, R1E<br/>         Fnd. ½" rod &amp; sq. stake.<br/>         N 20° W 8" Balsam 7.62' Ex.<br/>         S 28° E 9" Maple 19.25' Ex.<br/>         30' East of Trail.</p> | <p>(A-4) W. ¼ Cor. Sec. 7, T32N, R1E<br/>         Fnd. 1" bar<br/>         S 20° E 16" Cedar 17.82' Ex.<br/>         N 85° W 13" Cedar 17.10' Ex.<br/>         N 5° W 12" Cedar 29.35' Ex.</p> |
|---|--|

No evidence of original corner.

No evidence of original corner.

The Peer Group approved (A-3) & (A-4) as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |  |
|--|--|
| <p>A-3) S.W. Cor. Sec. 6, T32N, R1E<br/>         Placed Mont. Re-Mon. cap on ½" rod.<br/>         N 20° W 8" Balsam 7.62'<br/>         S 25° W 11" Maple 9.16'<br/>         S 28° E 9" Maple 19.25'<br/>         N 50° E 8" Maple 14.45'</p> | <p>(A-4) W. ¼ Cor. Sec. 7, T32N, R1E<br/>         1" bar<br/>         S 20° E 16" Cedar 17.82'<br/>         N 85° W 13" Cedar 17.10'<br/>         N 5° W 12" Cedar 29.35'<br/>         S 85° E 8" Cedar 11.60'</p> |
|--|--|

Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt

Date Dec 15, 1993

Surveyor's Michigan License No. 18660

