

Montmorency County Remonumentation

08136

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
MONTMORENCY CITY  
REGISTERED DEEDS  
DEC 20 10 12 AM '93  
A. PANOHAN-HELROY

For corners in

<u>Montmorency</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>32N</u> R <u>1E</u>	<u>A-7</u>
	T <u>32N</u> R <u>1E</u>	<u>A-8</u> ✓
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

APPROVED BY  
PEER GROUP

NOV 05 93

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Donald E. Marlatt, in a field survey on December 10, 1993, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- (A-7) S.W. Cor. Sec. 18, T32N, R1E  
Post Cor. set by Austin Burt 1850.  
Beech 12-S 46 W-19  
Beech 10-N 15 E-18  
Ironwood 7-S 80 E-6  
Beech 8-N 10 E-16  
Survey Sec. 13, T32N, R1W, Otsego Co.  
Survey records.
- (A-8) W. 1/4 Cor. Sec. 19, T32N, R1E  
Post Cor. set by Austin Burt 1850.  
Beech 12-S 60 W-42  
Beech 6-N 23 E-22

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (A-7) S.W. Cor. Sec. 18, T32N, R1E  
Fnd. 2" pipe in conc.  
Trail road West  
S 35° E 13" Basswood 33.35'  
N 73° E 12" Maple 21.75'
  - (A-8) No evidence of Cor.  
Set 1/2" rod & Re-Mon. cap.  
Set Cor. mid-point on line.
- No evidence of original corner.

The Peer Group approved (A-7) as the best available evidence of the original corner.

The Peer Group approved (A-8) as a careful and faithful establishment of the position of the corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (A-7) S.W. Cor. Sec. 18, T32N, R1E  
2" pipe in conc. Placed Co. Re-Mon cap.  
N 58° E 10" Maple 47.83'  
S 33° E 9" Maple 60.08'  
S 62° W 24" Oak 47.38'  
N 54° W 12" Beech 29.30'
- (A-8) Set 1/2" rod & Co. Re-Mon. cap.  
N 10° E 13" Oak 5.15'  
N 45° W 12" Oak 7.12'  
S 76° W 10" Oak 15.66'  
S 10° E 17" Oak 9.73'

Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt

Date Dec 15, 1993

Surveyor's Michigan License No. 18660

