

Montmorency County Remonumentation

08137

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
MONTMORENCY CITY
REGISTER OF DEEDS
DEC 20 10 12 AM '93

A. PANON-MCELROY
[Signature]

or corners in

Montmorency (County) Located In: Corner Code #
Public Land Survey T 32N R 1E
T 32N R 1E
A-9
A-10
APPROVED BY PEER GROUP
NOV 05 93

Register of Deeds Stamp & File Number

Lot No. , Recorded Plat
Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36.

Donald E. Marlatt, in a field survey on December 10, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- (A-9) S.W. Cor. Sec. 19, T32N, R1E Post Cor. set by Austin Burt 1850. Hemlock 10-N 32 E-9 Hemlock 8-S 21 W-14 Hemlock 6-S 24 E-9 Act 74 by Larry Gerschbacher L. 1, P. 78.
(A-10) W. 1/4 Cor. Sec. 30, T32N, R1E Post Cor. set by Austin Burt 1850. Pine 16-N 14 E-10 Pine 16-S 58 W-50 Survey by Duane MacNeill for Fletcher Nov. 1988.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (A-9) S.W. Cor. Sec. 19, T32N, R1E Fnd. 1/2" rod, appears to be G. De La Maters. 20" R. Pine S 40° W 77.96' 24" R. Pine N 56° W 55.53'
(A-10) W. 1/4 Cor. Sec. 30, T32N, R1E Fnd. 1/2" rod, appeared to be G. De La Maters. S 15° E 16" N. Pine 22.51'

No evidence of original corner. No evidence of original corner.

The Peer Group approved (A-9) & (A-10) as the best evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (A-9) S.W. Cor. Sec. 19, T32N, R1E Placed Co. Re-Mon. cap on 1/2" rod. N 53° W 24" N. Pine 55.51' S 60° W 20" Oak 37.11' S 44° W 20" N. Pine 78.11' N 81° E 12" Oak 45.7'
(A-10) W. 1/4 Cor. Sec. 30, T32N, R1E Placed Co. Re-Mon. cap on 1/2" rod. N 42° W 19" N. Pine 94.05' N 60° E 12" J. Pine 21.25' S 65° E 16" N. Pine 81.11' S 15° E 16" N. Pine 22.51'

Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

igned by Donald E Marlatt Date Dec 15, 1993

urveyor's Michigan License No. 18660

