

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

08128

RECEIVED
MONTMORENCY CITY
REGISTER OF DEEDS
DEC 20 10 12 AM '93

A. PANGAN-HELLROY

Donald E. Marlatt

For corners in

Montmorency
(County)

Located In:

Corner Code #/

1. Public Land Survey

T 32N R 1E

A-11 ✓
A-12

T 32N R 1E

T _____ R _____

T _____ R _____

**APPROVED BY
PEER GROUP**

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

NOV 0 5 93

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald E. Marlatt, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-11) S.W. Cor. Sec. 30, T32N, R1E
Post Cor. set by Austin Burt 1850.
Tamarack 8-S 33 W-15
Tamarack 8-N 55 E-25
Survey by Duane MacNeill for
Steve Fletcher Nov. 1988.

(A-12) W. ¼ Cor. Sec. 31; T32N, R1E
Post Cor. set by Austin Burt 1850.
Pine 16-N 2 W-54
Pine 6-S 1 W-20
Survey by Duane MacNeill for
Steve Fletcher Nov. 1988.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-11) S.W. Cor. Sec. 30, T32N, R1E
Fnd. ½" rod & 1" pipe with cap #19237
S 74° E 10" Cedar 34.71'
S 75° W 17" N. Pine 57.5'

(A-12) W. ¼ Cor. Sec. 31, T32N, R1E
Fnd. 1" pipe & cap #19237

No evidence of original corner.

No evidence of original corner.

The Peer Group approved (A-11) & (A-12) as the best available evidence of the reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-11) S.W. Cor. Sec. 30, T32N, R1E
Placed Co. Re-Mon. cap on ½" rod.
S 74° E 10" Cedar 34.71'
N 12° E 9" Spruce 27.54'
N 89° W 11" Spruce 36.95'
S 75° W 17" N. Pine 57.5'

(A-12) W. ¼ Cor. Sec. 31, T32N, R1E
Placed Co. Re-Mon. cap on 1" pipe.
S 7° E 10" N. Pine 21.07'
S 54° W 10" N. Pine 14.58'
N 50° E 15" Oak 45.30'
S 75° E 9" Maple 42.95'

Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt

Date Dec 15, 1993

Surveyor's Michigan License No. 18660

