

Montmorency County Re-monumentation

08139

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montmorency Located In: \_\_\_\_\_ Corner Code #A-13  
(County)

- 1. Public Land Survey T 32N R 1E \_\_\_\_\_ A-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**APPROVED BY  
PEER GROUP**

NOV 0 5 93

RECEIVED  
MONTMORENCY CITY  
REGISTERED DEEDS  
DEC 20 10 12 AM '93  
A. PANCAN-NEILROY

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	19		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald E. Marlatt, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-13) S.W. Cor. Sec. 31, T32N, R1E  
Post Cor. set by Austin Burt 1850.  
Pine 16-N 2 W-54  
Pine 6-S 1 E-20  
Survey by Duane MacNeill for Steve Fletcher Nov. 1988.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


(A-13) S.W. Cor. Sec. 31, T32N, R1E  
Fnd. conc. Mon. & 1" pipe with cap #19237 along side.  
S 48° E 16" Oak 70.0'  
S 75° W 24" N. Pine 50.85'  
N 45° E 10" J. Pine stp. 83.10' 1928 G.F. De La Mater tag.

No evidence of original corner.

The Peer Group approved (A-13) as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-13) S.W. Cor. Sec. 31, T32N, R1E  
Placed Co. Re-Mon. cap on conc. Mon.  
S 10° E 9" Maple 39.90'  
S 48° E 16" Oak 70.0'  
S 75° W 24" N. Pine 50.85'  
N 65° E 14" Oak 61.32'



Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt Date Dec 15, 1993  
Surveyor's Michigan License No. 18660