

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---|-------------------|
| 1. Public Land Survey | T <u>32N</u> R <u>2E</u> | <u>F-9, 6-8</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

CARL KIISKILA

March 24 97

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:
 F-9 6-8

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9

6-8

REESTABLISHED THE N 1/4 COR S-28, MIDWAY AND ONLINE BETWEEN CORNERS FND 1/2 MILE TO THE EAST AND WEST. THE CENTER OF A EAST-WEST TRAIL IS 6' SOUTH; CENTER OF TRAIL TO THE NORTH IS 17.5' EAST. EAST-WEST WIRE FENCE IS 1' NORTH.

FD AND ACCEPTED A 2" PIPE W/CONCRETE BASE AS ESTABLISHED BY MARCUS SCHAAF P.S. DURING A DEPT OF CONSERVATION SURVEY IN THE AREA. THE CENTER OF E-W TRAIL ROAD IS 29' SOUTH. THE CENTER OF N-S POWER LINE IS 27' WEST.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9

6-8

SET 1" X 36" I.P.I.PE W/ALUM CAP
 JACK PINE 8" N77E 45.14'
 JACK PINE 14" N01W 42.17'
 JACK PINE 8" N77W 39.02'
 RED PINE 9" S28E 27.90'
 SET CARSONITE POST, 1.0' NORTH

FOUND A 2" PIPE W/CONCRETE BASE
 10" OAK N82E 125.73'
 JACK PINE 4" S25E 52.16'
 JACK PINE SOUTH 58.01'
 PK NAIL P.POLE N59W 28.96'
 ADDED CARSONITE POST



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 8-20-97