

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

MONTMORENCY

(County)

Located in:

Corner Code #

- |                                    |                             |                   |
|------------------------------------|-----------------------------|-------------------|
| 1. Public Land Survey              | T <u>32N</u> R <u>2E</u>    | <u>E-11, 6-10</u> |
|                                    | T _____ R _____             | _____             |
|                                    | T _____ R _____             | _____             |
|                                    | T _____ R _____             | _____             |
| 2. Property Controlling in Section | S <u>28</u> T _____ R _____ | _____             |
|                                    | S _____ T _____ R _____     | _____             |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____     | _____             |
|                                    | S _____ T _____ R _____     | _____             |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

CARL KIISKILA

JUNE 4 1997

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:  
 E-11 \_\_\_\_\_ G-10 \_\_\_\_\_

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)



- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11

REESTABLISHED THE SW CORNER OF SEC. 28 BY DOUBLING OVER THE N 1/16 COR ON THE WEST LINE OF SECTION 33 FROM THE WEST 1/4 CORNER SECTION 33. THESE TWO CORNER POSITIONS WERE PREVIOUSLY ESTABLISHED BY MARCUS SCHAAF P.S. WHILE DOING A DEPT OF CONSERVATION SURVEY IN THE AREA.

G-10

FOUND AND ACCEPTED A 1" IRON PIN FOR THE EAST 1/4 CORNER OF SECTION 28. THIS PIN HAS BEEN ACCEPTED BY DON MARLATT P.S. AND OTHER SURVEYORS IN THE AREA. THE PIN IS LOCATED IN THE CENTER OF A N-S TRAIL ROAD GOING NORTH AND IS 13.5' NORTH OF A E-W RAIL FENCE.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11

SET 1" X 32" IP W/ ALUM DNR CAP. SET CARSONITE POST.  
 JACK PINE 5" N30°W 17.59'  
 JACK PINE 5" S35°W 27.55'  
 JACK PINE 8" S67°E 54.58'  
 RED PINE 12" N69°E 75.52'  
 N-S SMOOTH WIRE WEST 6.5'

G-10

FD 1" X 28" IRON PIN REPLACED WITH 4" X 36" CONC. MON  
 RED PINE 14" S71°W 46.29'  
 RED PINE 12" S36°E 32.68'  
 JACK PINE 6" N82°E 31.42'  
 JACK PINE 12" N22°E 53.01'  
 ADDED A CARSONITE POST

Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 8-20-97