

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

MONTMORENCY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 32N R 2E 6-9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S 28 T \_\_\_\_\_ R \_\_\_\_\_ 3  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

CARL KIISKILA

JUNE 8

97

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

3

6-9

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3

6-9

RESET MARCUS SCHAAF'S 1 1/4" PIPE WITH CONC BASE FOR THE SW COR OF THE NW 1/4 OF THE NW 1/4 SEC 28 TO FIT STANDARD BLM INSTRUCTIONS FOR SUBDIVISION OF A SECTION. CORNER FALLS UNDER N-S SMOOTH WIRE FENCE. CENTER N-S TRAIL ROAD IS 8' EAST.

FOUND AND ACCEPTED A 2" PIPE W/CONC. BASE FOR THE N.E CORNER OF SEC. 28 AS SET BY MARCUS SCHAAF P.S. DURING A DEPT OF CONSERVATION SURVEY IN THE AREA. THE MONUMENT FALLS IN A E-W TRAIL ROAD AND IS 25' EAST OF N-S POWER LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3

6-9

RESET MARCUS SCHAAF'S MON.  
 JACK PINE 4" N27°W 20.58'  
 JACK PINE 3" S48°W 32.59'  
 JACK PINE 7" S66°E 29.15'  
 JACK PINE 7" N77°E 25.22'

FOUND 2" IP (SCHAAF MON)  
 JACK PINE 7" S86°W 47.31'  
 JACK PINE 8" N45°W 75.03'  
 JACK PINE N35°E 42.47'  
 JACK PINE S36°E 72.47'  
 SET CARSONITE POST 545 W 33.00'  
 CL OF TRAIL ROAD E-W & N-S 25'



Signed by Carl T. Kiiskila  
 Surveyor's Michigan License No. 33981

Date 8-20-97