

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T...32 NR...3 E..

----- Montmorency ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 17-18-19-20 ---

DESCRIPTION OF CORNER MONUMENT 1" pipe with a 4" brass cap -----

WITNESSES TO CORNER --- 9" Maple ----- S 71 W ----- 59 links -----

--- 8" Ironwood ----- N 13 W ----- 26 1/2 links .

--- 6" Beech ----- S 69 E ----- 30 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Could make no positive identification of Beech and Maple government BTs. Corner was established by proportionate measurement on a calculated straight line between corners 1 mile east and 1 mile west. This latitude checks, as near as can be determined, the calls of the government record to the swamp edge south.

Corner was placed and witnessed November 13, 1958.

SURVEYORS SEAL

SIGNED

Kenneth J. Betting
REGISTERED LAND SURVEYOR

DATE 11/18/58