

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T..32. NR..3 E..

----- Montgomery ----- COUNTY

DESCRIPTION OF CORNER ... 1/4 Corner common to Sections 19 and 20 -----

DESCRIPTION OF CORNER MONUMENT ... 1" pipe with a 4" brass cap -----

WITNESSES TO CORNER ... 9" Cedar ----- S 73 E ----- 48 links -----

... 11" Cedar ----- N 13 W ----- 41 1/2 links ..

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a survey in this area. Could not satisfactorily identify the government BTs after considerable search. This point conforms exactly with old line markings in longitude, one of which was determined to be at least 80 years old, and others about 35 years old. Checks swamp edges north and south fairly good, as near as they can be presently determined.

Corner was placed and witnessed November 13, 1958.

SURVEYORS SEAL

SIGNED

*Kenneth J. Deering*  
REGISTERED LAND SURVEYOR

DATE 11/19/58