

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T..32. NR...3E.

..... Montmorency..... COUNTY

DESCRIPTION OF CORNER 1/8 Corner at center of NE 1/4 Section 20

DESCRIPTION OF CORNER MONUMENT 1" x 24" pipe

WITNESSES TO CORNER 8" Birch N 49 W 40 1/2 links

10" Birch N 32 E 10 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by survey procedure at the calculated center of the NE 1/4 of Section 20, by Forestry Division survey crew. Set at midpoint on line between N 1/8 corners on the east line of the Section and the N - S 1/4 line. Checked by line from the E 1/8 corner on the north side of Section 20. See Survey of Section 20 for more information.

Corner was placed and witnessed November 25, 1958.

SURVEYORS SEAL

SIGNED Kenneth J. Ostling DATE 11/25/58
REGISTERED LAND SURVEYOR