

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T..32 NR.3E..

----- Montmorency ----- COUNTY

DESCRIPTION OF CORNER -- Section Corner common to Sections 16-17-20-21 --

DESCRIPTION OF CORNER MONUMENT 1" pipe with a 4" brass cap -----

WITNESSES TO CORNER -- 6" B. Ash ----- S 2 1/2 E ----- 39 links -----

-- 9" Elm ----- N 26 E ----- 48 1/2 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Found a very old square post at corner supported by probable government BT NW. Checks government record west to swamp edge and south to stream crossing. One of the few corners in this area which has any probable support so was accepted as the corner in this survey.

Corner was placed and witnessed November 12, 1958.

SURVEYORS SEAL

SIGNED Kenneth J. Oetting DATE 11/19/58
REGISTERED LAND SURVEYOR