

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 32. NR. - - 2 E.  
T 32 NR 3 E

----- Montmorency ----- COUNTY

DESCRIPTION OF CORNER ----- Section Corner common to Sections 13-24-18-19. -

DESCRIPTION OF CORNER MONUMENT ----- 1" pipe with a 4" brass cap. -----

WITNESSES TO CORNER ----- 14" R. Pine ----- S. 11 E ----- 189 1/2 links.

----- 14" R. Pine ----- West ----- 256 1/2 links.

----- 7" Aspen ----- N 49 E ----- 8 1/2 links.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Government BTs removed in fire line construction. Set corner on line over 1/4 and section corner west, which are good government corners, making the east 1/2 mile equal to the west 1/2 mile between 13 and 24. Corner falls in N-S fire line road. This position was considered more in conformity with the calls of the government survey, since a single proportion on the town line between corners 1 mile north and 2 1/2 miles south, which cannot be identified as government corners, would place the corner of 18-19-13-24 about 65 links north of our established position and far beyond the usual inconsistency of the government survey. This position is further supported by line tree sites in the east 1/2 mile between 13 and 24.

Corner was placed and witnessed November 12, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting* DATE 11/19/58  
REGISTERED LAND SURVEYOR