

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 32. NR. 3 E.

----- Montmorency ----- COUNTY

DESCRIPTION OF CORNER . Section Corner common to Sections 20-21-28-29 . . .

DESCRIPTION OF CORNER MONUMENT . . 1" pipe with a 4" brass cap . . . . .

WITNESSES TO CORNER . . 8" Maple . . . . . S 86 W . . . . . 37 1/2 links . .

. . 10" Maple . . . . . N 12 E . . . . . 36 links . . . . .

. . 12" Basswood . . . . . S 57 E . . . . . 62 links . . . . .

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Set corner at proportionate measure between section corners 1 mile east and 2 miles west, at government measure from section corner north. This latitude conforms very good with stream crossing north and swamp edge south. The 1/4 and section corners south appear to fall in Rush Lake backwaters so did not expect to improve on the location of this corner by lines to the south.

Corner was placed and witnessed November 13, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Osling* . . . . . DATE 11/19/58  
REGISTERED LAND SURVEYOR