

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

(County)

Located In: Corner Code ≠#

1. Public Land Survey	T <u>32N</u> R <u>3E</u>	<u>K-1, K-2</u>
	T <u> </u> R <u> </u>	<u>L-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL KIISKILA, in a field survey on JUNE 5, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1	K-2	L-1
FD IRON AS USED BY P.S. D.MARLATT IN CERT. OF SURVEY Li.3, Pg.327 FOR NW COR OF S-1. 20" CEDAR NOS W, 30.22' IS SAID TO BE DBT BY D.MARLATT (US = CEDAR 6, N12°W 46 LKS. - 30.4'). FD 2 WOODEN POST POINTS BESIDE IRON (APPROX. 1' BELOW WATER). MON IS AT FENCE CORNER, SMOOTH WIRE E-W & N.	FD 1/2" ROD AS SET BY D.MARLATT IN 1985, CERT. OF SURVEY Li.3, Pg.327. COR FITS SP TO US GLO RUNOUT POSITION.	FD R.BISCHER IRON & CAP AND OLD 3" SQUARE CEDAR POST FOR N1/4 COR S-1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1	K-2	L-1
FD 1/2" IR ROD, SET 1"x 48" IR PIPE/BNR MON & CARSONITE POST. #20" CEDAR N05°W 30.22' #19" CEDAR N29°E 17.12' #PINE STUB CHARRED W/OLD BLAZE N40°E 20.4' #12" CEDAR S47°E 34.41' #14" CEDAR S19°W 28.02' OLD WIT BY OTHERS #WIT BY D.MARLATT, 818660	FOUND 1/2" IR ROD W/CAP- D.MARLATT, INSIDE 4" STEEL PIPE & SET CARSONITE POST. 4" BALSAM S47°E 33.17' 4" BALSAM S03°W 23.16' 4" BALSAM S59°W 29.55' 6" MAPLE N77°W 14.13' CTR E-W SAND RD NORTH 16.9'	FD 1/2" IR W/R.BISHER CAP, PLACED 1"x 36" PIPE OVER IR. & SET CARSONITE POST. #7" MAPLE N62°W 12.20' #8" MAPLE N14°W 23.31' #8" MAPLE N70°E 3.79' 5" MAPLE S37°W 31.76'

= OLD WIT. BY R.BISCHER



Signed by Carl T. Kiiskila Date 2-27-97

Surveyor's Michigan License No. 33981