

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MONTGOMERY
 (County)

Located In: _____ Corner Code ~~##~~

- | | | |
|------------------------------------|--------------------------|-----------------|
| 1. Public Land Survey | T <u>32N</u> R <u>3E</u> | <u>K-8, L-8</u> |
| | T _____ R _____ | <u>M-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24	25	26	27	28	29	30
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CARL KIISKILA, in a field survey on AUGUST 8, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 K-8 L-8 M-8

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | | |
|---|--|--|
| K-8
REESTABLISHED THE W1/4 COR OF SEC 24 MIDWAY AND ON LINE BETWEEN THE FOUND NW COR S-24 AND REESTABLISHED SW COR SEC. 24. | L-8
ESTABLISHED THE CTR. OF SEC 24 AT INTERSECTION OF 1/4 LINES. FENCE CORNER, SMOOTH WIRE N & E IS 22' EAST & 9' SOUTH. | M-8
REESTABLISHED THE E1/4 COR OF SEC 24 MIDWAY BETWEEN THE FD SE & NE COR'S OF SEC 24 AND ON LINE BETWEEN FD W1/4 COR S-19 (T32N-R4E) & REESTABLISHED NW COR S-19. N-S SMOOTH WIRE IS 2'+/- EAST, FENCE COR (ONE OLD & ONE NEW CEDAR POST) WITH SMOOTH WIRE & SOME CEDAR POSTS TO N & W IS 39' SOUTH. |
|---|--|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|---|--|
| K-8
SET 1"x 60" IRON PIPE W/DNR ALUMN. CAP.
4" MAPLE S30°W 25.27'
8" CEDAR S89°W 6.53'
6" SPRUCE N19°E 18.02'
8" CEDAR S81°E 4.43'
SET CARSONITE POST NORTH 1.17' | L-8
SET 1"x 32" IRON PIPE W/DNR ALUMN. CAP AND CARSONITE POST.
4" MAPLE N39°E 15.81'
10" OAK S84°E 30.46'
6" OAK S02°W 48.71'
4" MAPLE N84°W 24.27' | M-8
SET DNR MON & CEDAR POST.
5" TRI.MAPLE N25°W 14.65'
13" R.OAK EAST 10.67'
4" MAPLE S40°W 9.16'
12" R.OAK N80°W 30.73'
W1/4 COR S-19, T32N-R4E, FD PIPE REPLACED WITH DNR MON IS S01°17'18"E 328.44' |
|--|---|--|



Signed by Carl T. Kiiskila Date 2-27-97
 Surveyor's Michigan License No. 33981