## SURVEY & REMONUMENTATION

Montmorency County Remonumentation Liber 00012 Page 0137

APR 2 4 1995

For co@GMMISSION

5. Private Claims .

expressed below:

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN MONTMORENCY COUNTY Recorded & Filed

11-10-1994 14:14:16

A. PANGAN-MCELROY

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

10

11

12

Montmorency Located in: Corner Code ## (County) Montmorency Township T 32 N R 3 E A-5 1. Public Land Survey T \_\_\_\_ R \_ T APPROVED BY \_\_R\_PEER GROUP 2. Property Controlling \_ T ..... R \_ \_\_ T \_\_\_\_ R \_\_\_\_AUG 0 5 in Section Miscellaneous \_\_ T \_\_\_\_ R \_\_ Property in Sec. \_ T \_\_\_\_\_ R \_\_

Don Marlatt November 8 , in a field survey on do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Lawland/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- (A-5)S.W. Cor. Sec. 7, T 32 N, R 3 E

Original post set by Hiram Burnham July, 1850.

\_ , Recorded Plat \_

10" Cedar N 60° W 20 links

6" Cedar S 20° W 15 links

Schaaf - DNR Survey - No Date.

D. Porter - Recorded Act 74, L. 1, P. 397 on July 22, 1987.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (A-5)S.W. Cor. Sec. 7, T 32 N, R 3 E

Found 2" pipe in concrete & 4" x 4" stake - 201 = East of trail.

10" Cedar N 28° W 8.27'

8" Cedar N 77° E 9.71

8" Cedar S 11° E 2.5'

12" Cedar S 82° W 15.8'

No evidence of original corner.

Accepted as a careful and faithful establishment of the position of the corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- S.W. Cor. Sec. 7, T 32 N, R 3 E (A-5)Left 2" pipe & concrete in place. Placed Remonumentation Cap.

10" Cedar N 28° W 8.07'

12" Cedar S 82° W 15.55'

8" Cedar S 11° E 2.17'

8" Cedar N 77° E 9.70"

Witnesses marked with a 30 penny spike & I.D. tag #18660.



Signed by Donald & Marlatt Date 11-9-

Surveyor's Michigan License No. \_\_\_\_18660

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1

REVISED JAN., 19