

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montmorency COMMISSION (County)

Located in: Montmorency Twp. Corner Code #

STATE OF MICHIGAN MONTMORENCY COUNTY Recorded & Filed

11-02-1994 15:46:54

A. PANGAN-MCELROY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 32N R 3E (A-9)
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

APPROVED BY PEER GROUP

MAY 13 94

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-K and rows 1-13. A dot is marked at row 9, column A.

I, Larry G. Beauregard in a field survey on March, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land-Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-9) GLO post set by Hiram Burnham July 5, 1850. Wits: Lynn 14" S 45° W 33 links Hemlock 16" N 55° W 50 links Ken Ostling P.S. #10068 in 1958 set DDC std. corner & filed Forestry Division Land Corner Record. Witnesses marked: (11" W. Ash S 61° W 89 links) (10" Maple N 45° W 69 1/2 links) (10" R. Oak S 55° E 71 1/2 links). Note: Ostling established this corner by proportionate measurement between corners 1 mile North and 1 1/2 miles South by Forestry Division survey crew while making a survey in this area. Could not identify Beech and Hemlock Gov't. B.T.'s, probably removed in road construction.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-9) Found 1" pipe with a 4" brass cap in good condition 4" below road surface. (DDC standard corner).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-9) Sec. Cor. Comm. to Sec's 24 & 25, T32N, R2E & Sec's 19 & 30, T32N, R3E. Ex. Department of Conservation 1" pipe & 4" brass cap, 4" below road surface. Accepted as the best available evidence of the re-establishment of the original corner. Approved by the Peer Group on May 13, 1994. S 61° W 58.74' (R) 59.0' (M) to spike 16" W. Ash N 45° W 45.87' (R) 46.0' (M) to spike 14" Maple S 55° E 47.19' (R) & (M) to spike 10" R. Oak S 85° E 36.47' (M) to spike 8" Maple

Placed blaze, 20 penny spike & P.S. tag #18654 (typ)

Signed by Larry G. Beauregard Date 11/2/94
Surveyor's Michigan License No. 18654

