

SURVEY & REMONUMENTATION

Montmorency County Remonumentation

Liber **00012** Page **0119**

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
Montmorency
(County)

Located In: Montmorency Corner Code ##
Twp.

STATE OF MICHIGAN
 MONTMORENCY COUNTY
 Recorded & Filed

11-02-1994 15:47:06

A. PANGAN-MCELROY
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 32N R 3E (A-10)
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**APPROVED BY
 PEER GROUP**

MAY 13 94

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Larry G. Beauregard in a field survey on March, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-10) GLO marked W. Pine 40" $\frac{3}{4}$ post by Hiram Burnham July 5, 1850.
 Wit: Beech 14" S 65° W 20 links

Ken Ostling P.S. #10068 in 1958 set DOC std. corner & filed Forestry Division Land Corner Record.

Witnesses marked: (9" R. Oak N 85° E 25 links) (7" R. Oak S 44° W 59 links).

Note: Ostling established this corner by proportionate measurement between corners $\frac{1}{2}$ mile North and 1 mile South by Forestry Division survey crew while making a survey of this area. Stumps or sites of 4 large W. Pines within radius of 40 links of our position, but none supported by Gov't. Beech witness and none can positively be identified as the Gov't. $\frac{1}{4}$ corner tree.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10) Found 1" pipe with a 4" brass cap in good condition and witnesses by Ostling. This corner is 566'± West of Co. Rd. #628. (DOC standard corner).



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10) $\frac{1}{4}$ Cor. Comm. to Sec's 25 & 30, T32N, R2E & T32N, R3E.

Ex. Department of Conservation 1" pipe & 4" brass cap, 6" above ground good condition.

Accepted as the best available evidence of the re-establishment of the original corner. Approved by the Peer Group on May 13, 1994.

N 85° E 16.50' 17" R. Oak (R) (NBT)

N 55° E 62.60' 13" Hemlock

S 50° W 38.94' 15" R. Oak (R) (NBT)

N 25° W 13.82' 5" Maple

565'± East to Co. Rd.

(Placed blaze, 20 penny spike & P.S. tag #18654) (typ)

Signed by Larry G. Beauregard Date 11/2/94
 Surveyor's Michigan License No. 18654