

SURVEY & REMONUMENTATION **Montmorency County Remonumentation**

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber **00012** Page **0120**

For corners in
COMMISSION
Montmorency
(County)

Located in: Montmorency Corner Code #1
Twp.

STATE OF MICHIGAN
 MONTMORENCY COUNTY
 Recorded & Filed

11-02-1994 15:47:19

A. PANGAN-MCELROY
 REGISTER OF DEEDS

- 1. Public Land Survey T 32N R 3E (A-11)
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**APPROVED BY
 PEER GROUP**

MAY 13 94

[Signature]

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Larry G. Beauregard in a field survey on March, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-11) GLO post set by Hiram Burnham July 4, 1850.

Wits: Y. Pine 5" S 30° W 28 links

Y. Pine 5" N 35° W 12 links

Ken Ostling P.S. #10068 in 1958 set DOC std. corner & filed Forestry Division Land Corner Record.

Witnesses marked: (12" R. Pine N 20° W 207 links) (8" W. Oak N 45° E 139 links) (5" J. Pine S 66° W 61½ links).

Note: Ostling established this corner by proportionate measurement between corners 2 miles North and ½ mile South by Forestry Division survey crew while making a survey in this area. Aspen Gov't. B.T.'s all gone. Checks fair stream crossing North and exactly with North edge of open marsh.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-11) Found 1" pipe with a 4" brass cap in good condition and witnesses by Ostling. This corner is 142'± East of Co. Rd. #628. (DOC standard corner).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11) Sec. Cor. Comm. to Sec's 25 & 36, T32N, R2E, & Sec's 30 & 31, T32N, R3E.

Ex. Department of Conservations 1" pipe & 4" brass cap, 6" above ground in good condition, 142'± E. of Co. Rd. 628. Accepted as the best available evidence of the re-establishment of the original corner. Approved by the Peer Group on May 13, 1994.

- N 10° W 136.62' (R) 136.81' (M) to spike 23" R. Pine
- N 45° E 91.74' (R) & (M) to spike 15" W. Oak
- S 70° W 40.59' (R) & (M) to spike 12" J. Pine
- S 45° E 68.53' (M) to spike 13" R. Oak

Placed blaze, 20 penny spike & P.S. tag #18654 (typ)

Signed by Larry G. Beauregard Date 11/2/94
 Surveyor's Michigan License No. 18654

