

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 32 N. R. 4E


Montmorency COUNTY

DESCRIPTION OF CORNER Sec. corner common to sections 30-31 on W. Boundary of Township

CORNER MONUMENT Set 1" pipe with 1/4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 13, 1966

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

2 1/4" Y Pine Stump N 28 W 25.3'

30" W. Pine Stump S 80 E 58.4'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey of Section 30. Set corner by proportionate measurement between good original corners 1 mile north and 1 mile south. Could not positively identify USBTs but this point checks the U. S. record for swamp and stream crossings north and south and east. Our corner falls about 75 links south and 20 links west of a squared post, set by unknown, but does not check for measurements along Section 30 and 31.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE May 17, 1966
REGISTERED LAND SURVEYOR #10068