

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MONTROSE
 (County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|-----------------------------|-----------------|
| 1. Public Land Survey | T <u>32N</u> R <u>4E</u> | <u>A-6, B-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>18</u> T _____ R _____ | <u>5, 8</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on OCTOBER 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 A-6 _____ B-6 _____ 5 _____

(NO EVIDENCE OF G.L.D. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.D. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 REESTAB'D N 1/4 COR S-18 SP TO US GLO MEAS (GEO. H CANNON) ON TWP LINE BETW REESTAB SW COR S-18 & FB NW COR S-18. SINGLE STRAND OF SMOOTH WIRE (ON TREES, GRD & SOME OLD CED POSTS) TO N & S IS 6' EAST. WINDING DRIVABLE TRAIL RD TO N & SW IS 200' + 30' WEST. WINDING TRAIL N & SE (NOT USED) IS 100' +/- E.	B-6 ESTAB'D CTR OF S-18 AT INTERSECTION OF 1/4 LINES. ONE STRAND OF SMOOTH WIRE, E-W, IS 22' SOUTH.	5 ESTAB'D NW COR OF SW 1/4 OF NE 1/4 S-18 PER STANDARD BLM INSTRUCTIONS. COR FALLS IN SWAMP, 150' - 200' S TO SW EDGE OF SWAMP.	8 ESTABLISHED SE COR OF FRL SW 1/4 OF FRL NW 1/4 PER STANDARD BLM INSTRUCTIONS. COR OF SINGLE STRAND SMOOTH WIRE TO E & N IS 6' N & 170' WEST.
---	---	---	--

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 SET DNR MON & CED POST. 7" MAPLE N65°W 27.22' 7" TRIPL MAPLE N40°E 56.96' 4" WHITE PINE S70°E 56.87' 14" TWIN MAPLE S30°W 26.44' E 1/4 COR S-13, T32N-R3E, SET DNR MON N01°22'23"W 280.39'	B-6 DROVE 1" X 48" GALV PIPE W/PS CAP. SET CED POST W/LOC TAG. 8" TM MAPLE N75°W 14.98' 15" MAPLE N30°E 20.83' 7" MAPLE S35°E 4.54' 11" MAPLE S35°W 27.86'	5 DR 1" X 96" GALV PIPE W/PS CAP & SET CED POST W/LOC TAG. 12" CEDAR N08°W 47.86' 7" CEDAR N40°E 51.26' 2" ASH S40°E 9.68' 10" CEDAR S18°W 32.71'	8 DR 5/8" X 34" REROD W/PS CAP. 13" SUGAR MAPLE N40°W 6.85' 2" W PINE N40°E 9.93' 8" TWIN MAPLE S50°E 13.30' 9" MAPLE (CLP 3) S05°W 17.64'
---	--	---	--

Signed by Carl T Kiiskila Date 2-27-97
 Surveyor's Michigan License No. 33981