

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MONTMORENCY
(County)

Located In:

Corner Code ≠

1. Public Land Survey	T	<u>32N</u>	R	<u>4E</u>	<u>B-7, C-7</u>
	T		R		<u>C-8</u>
	T		R		
	T		R		
2. Property Controlling in Section	S	<u>18</u>	T		<u>16</u>
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, C.T. KIISKILA, in a field survey on OCTOBER 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-7 C-7 C-8

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 REESTABLISHED S 1/4 COR S-18 PRORATED TO U.S. GLD RUN OUT BETH FD SE COR S-18 & REESTAB'D SW COR S-18. FD OLD 1 1/2" PIPE S86°53'N, 248.0'.	C-7 FD & ACCEPTED 1 3/4" PIPE FOR NE COR S-19. PS D.PORTER FD & RECORDED THIS COR IN 1973. FN REMAINS (FN ALL DOWN) TO E-W-S.	C-8 FD 1 3/4" PIPE FOR E 1/4 COR S-19. SINGLE STRAND OF SMOOTH WIRE TO NORTH & WEST. PS D.PORTER FD 2" PIPE HERE IN 1973. (WE FD STUMP OF ONE OF HIS WITS, ASPEN NN, FITS OK).	16 ESTABLISHED SW COR OF SE 1/4 OF SE 1/4 OF S-18 PER STANDARD BLM INSTRUCTIONS. E-W TRAIL IS 246' NORTH.
---	---	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 DROVE 1" X 60" GALV PIPE W/ALUM BNR CAP. SET CED POST. 11° CEDAR N50°W 26.88' 8° CEDAR N02°E 36.98' 9° CEDAR N35°E 37.59' 6° SPRUCE S50°W 8.49'	C-7 FD 1 3/4" PIPE. SET CED POST. 118° R PINE N03°E 35.02' 118° MAPLE N48°E 29.31' 5" W BIRCH N58°W 13.73' 4" BALSAM S14°W 16.46' TREES HAVE UPPER & LOWER BLAZE	C-8 FD 1 3/4" X 25" PIPE (ABOVE GRD) AT FENCE CORNER. 6" POPLAR N73°E 30.58' 12" R PINE S40°W 29.58' 4" CHERRY S31°E 28.55' 4" POPLAR N57°W 52.50' W EDGE 2-TRACK EAST 42.5'	16 DR 5/8" X 34" REROD W/PS CAP. SET CED POST W/LOC TAG. 4" MAPLE N80°W 5.68' 4" MAPLE N60°E 6.22' 6" MAPLE S65°E 14.05' FD OLD 1 1/4" PIPE S86°20'W 111.6'
---	---	--	---

OLD WITNESS
 118. PORTER WITNESSES

Signed by Carl T. Kiiskila Date 2-27-97
 Surveyor's Michigan License No. 33981

