

1997 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00002 Page 0089

For corners in

<u>Alpena</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 32N R 05E	A07
	T 32N R 04E	M07
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
County of Alpena
Recorded
08-25-1997 12:00:16
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on March 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1856: Josiah Knauer Set Cedar post. Witnesses given: Tamarack 8 S 59° W 46, Cedar 10 N 57° W 33.
- 1889: William Leroy No monumentation given. Witnesses given: Cedar 8 S 59° W 46, Cedar 10 N 57° W 33, Cedar 6 S 16° E 6, Cedar 7 N 35° E 38.
- 1895: William Leroy Found original corner. Set 2" square Cedar stake. Witnesses given: Cedar 8 S 59° W 46, Cedar 6 S 16° E 6, Cedar 7 N 35° E 38.
- 1983: Ronald Bischer, P.S. Found 1" bar at intersection. Ronald Bischer recorded LCRC at Liber 1, page 156. Witnesses given: N 08° W 45.71' Road Sign, N 55° E 46.90' Fence Corner, S 38° E 51.00' Telephone Pole.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Set 1/2" rerod next to found 1" bar in intersection.

SURVEY &
REMONUMENTATION

JUL 30 1999

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/1/97
D. B. Lewis

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on set 1/2" rerod, 6" below road surface.



- Witnesses given:
- N 40° E 47.45' Fence Corner (found tag #15410)
 - N 15° E 155.45' Power Pole
 - S 15° E 154.65' Power Pole
 - S 30° E 81.60' Fence Post

Signed by *Wayne T. Lewis*
Surveyor's Michigan License No. 41922

Date August 21, 1997