

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Montmorency Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey		T	<u>32N</u>		R	<u>4E</u>		B-1
		T	<u>32N</u>		R	<u>4E</u>		B-2
2. Property Controlling in Section	S	T	_____		R	_____		_____
	S	T	_____		R	_____		_____
3. Miscellaneous Property in Section	S	T	_____		R	_____		_____
	S	T	_____		R	_____		_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on August, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6											
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

B-1 G.L.O. John Hodgson D.S. 1840  
 Set quarter section post  
 Wit: Cedar 12 N74°E 10 links  
 Pine 18 N56°W 21 links

B-2 This corner position was not established during the original government survey.

Joshiah Knauer D.S. 1856 (Remeasured) old quarter section post re-established.

B-13 T.33N.,R.4E. Pg. 665 Presque Isle County land corner records (Delmer E. Porter P.S. #15410 April 1985). Found 2 old square stakes and 2 O.B.T. Stumps in place set 1/2" rod.

Wit: S05°E 17.01' 5" Cedar  
 N08°W 7.23' 6" Cedar  
 N70°W 15.55' 6" Cedar

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

B-1 Found 1/2" capped rod P.S. #15410 Delmer Porter and squared post.

B-2 Established the center of section 6 at the intersection of the N-S and E-W one-quarter lines.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B-1 Set D.N.R. Monument over found 1/2" capped rod

Wit: 6" Cedar N05°E 7.42'  
 5" Cedar S09°E 16.74'  
 6" Cedar N72°W 15.66'  
 5" Cedar N85°E 22.76'  
 Carsonite Post North 1±  
 E-W Smooth wire

B-2 Set 1" X 32" iron pipe with P.S. cap #33981

Wit: 10" Cedar S47°E 23.63'  
 5" Cedar N70°E 8.95'  
 4" Cedar N49°W 9.66'  
 4" Cedar S29°W 14.88'  
 Carsonite Post North 1±

Signed by: \_\_\_\_\_

*Carl T. Kiiskila*

Date: \_\_\_\_\_

1-10-02

Surveyor's Michigan License No.: \_\_\_\_\_

33981

