

SURVEY & REMONUMENTATION

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA H. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT of Act 74, Mich. P.A. 1970 '00 FEB 28 PM 1 09

Linda M. Brown

VOL. 2 280

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>11W</u>	<u>C-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on February 12, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 31, Ensley Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. N. Brookfield 1836
10" Beech N73°E 19 Links (12.54')#1
18" Peppercage N52°W 43 Links (28.38')#2

Delos G. Anderson (County Surveyor)
April 8 thru 12, 1902 Book A, Pages 345 and 346
County Surveyor's Witness Book Page 140
25" Pine Stump N28½°W 81 Links (53.46')#3

Delos G. Anderson (County Surveyor)
Book A, Page 193 January 18 and 19, 1897
Old Government Corner

Lyle S. Shepherd R.L.S. #503
Witness Book Number 2, Page 170
Square Wood Stake and 4 - 12" files
12" White Oak N50°W 42.7' #4
Kent County Corner (¾" Pipe) 117.5' East #5

Newaygo County Road Commission Sheet
1922 Square Oak Stake and 4 - 12" files
12" White Oak N50°W 42.7' #4
10" Oak N51°E 35.2' #6
24" Oak S25°W 132.50' #7

OVER ↙

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 4" Harrison cast iron monument marked "County Surveyor". The centerline of the East and West bituminous road is 2 feet ± North and the centerline of the gravel road going North is 12 feet East. The condition of the recorded witnesses are: #1 thru #4 gone, #5 good condition, #6 thru #8 gone, #9 and #10 good condition, #11 and #12 gone, #13 and #14 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 4" Harrison cast iron monument marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

North One Quarter Corner, Section 6, Solon Township, 4" diameter Monument with Kent County brass cap, East 117.20' #5
Centerline of Street Sign Post N50°E 64.93' #9
16" Red Oak N30°W 62.57' Set spike with tag #22439 in Southwesterly side of tree. #10
16" Cherry S52°E 103.65' Set spike with tag #22439 in Southwesterly side of tree. #13
Centerline of road going North is 12' East #14

Signed by Norman L. Ochs Date August 16, 1999
Norman L. Ochs
Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on August 19, 1999
Norman L. Ochs, County Representative.

Revised May 14, 1975
Revised Jan., 1983

N. L. O.



A. Description (cont.)

Patrick A. Salisbury R.L.S. #13594

August 27, 1970 Found Axle Shaft 1.3 feet down. Raised with a 1" Pipe. Centerline of road going North is 12 feet East and in the centerline of the East and West road.

30" Oak N50°W 42.2' #4

Telephone Pole N60°W 53.5' #8

Street Sign Post N45°E 65.15' #9

Kent County Corner East 116.65' #5

**SURVEY &
REMONUMENTATION**

MAR 1 8 2000

SECTION

Glen S. Hackbardt R.L.S. #25844

LCRC #526 April 1981

1" Iron at road intersection

12" Oak N50°W 42.05' #4

8" Oak N30°W 62.5' #10

8" Maple N75°W 102.25' #11

8" Triple Willow S80°W 78.71' #12

Norman L. Ochs R.L.S. #22439

LCRC #688 September 25, 1985

Found 1/2" Rod and 1" Pipe by using witnesses, in centerline of gravel road going East and West. Removed Rod and Pipe and set a 4" x 30" Harrison cast iron monument marked "County Surveyor".

8" Red Oak N30°W 62.48' #10

8" Triple Willow S80°W 78.71' #12

Sign Post N45°E 65.00' #9

6" Cherry S55°E 103.33' #13

Centerline of road going North is East 12' #14

North One Quarter Corner, Section 6, Solon Township, Kent County, East 117.22' #5

Norman L. Ochs R.L.S. #22439

June 15, 1989 Drawing Number 89122B

Found Harrison Monument

8" Red Oak N30°W 62.48' #10

8" Triple Willow S80°W 78.71' #12

6" Cherry S55°E 103.33' #13

8" Maple N75°W 102.25' #11