

SURVEY & REMONUMENTATION

MAR 1 3 2000

SECTION

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

00 FEB 28 PM 1 09

Linda M. Brown

VOL. 2

282

Register of Deeds Stamp & File Number

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T 11N R 11W</u>	<u>E-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Norman L. Ochs, in a field survey on February 11, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Corner, Section 32, Ensley Township, Newaygo County, Michigan.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. N. Brookfield 1836 12" Beech N54°E 70 Links (46.2') #1 14" Beech N37°W 28 Links (18.48') #2	Kent County Road Commission 1938 Stone Southwest Tower Leg North - Northeast 63.5' #3 Corner Post South - Southeast 27.0' #4 20" White Oak East - Northeast 119.8' #5
Delos G. Anderson (County Surveyor) Book A, Page 193 January 18 and 19, 1897 Old Government Corner	1907 William & Works Found Stone, shows 70 feet East to North One Quarter Corner, Section 5, Solon Township
1909 William & Works Found stone, shows 70.8 feet East to the North One Quarter Corner, Section 5, Solon Twp. #8	

OVER

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 4" Harrison cast iron monument marked "County Surveyor" 0.6 feet ± below bituminous. The centerline of the East and West bituminous road is 2 feet North and the centerline of the gravel road going North is 6 feet West. The condition of the recorded witnesses are: #1 thru #4 gone, #5 good condition, #6 gone, #7 and #8 good condition, #9 gone, #10 and #11 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 4" Harrison cast iron monument marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

48" White Oak N80°E 120.10' Set spike with tag #22439 in Northwesterly side of tree. #5
Power Pole S70°W 109.97' Found spike in Northwesterly side of pole. #7
North One Quarter Corner, Section 5, Solon Township, Monument with Kent County brass cap, East 70.80' #8
Centerline of Street sign pole N18°W 56.31' #10
Power Pole S65°E 136.96' Found concrete nail in Northeasterly side of pole. #11

Signed by Norman L. Ochs Date August 16, 1999
Norman L. Ochs

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on August 19, 1999
Norman L. Ochs, County Representative.

N.L.O.



Revised May 14, 1975
Revised Jan., 1983

A. Description (cont.)

Patrick A. Salisbury R.L.S. #13594

December 10, 1973 Dug and found 18 rocks. Found one stone that came to a point on old 1938 witness. I also found the Southwest Corner of Tower Leg cut off at ground. Fence Post witness was hit. 20" White Oak okay. Corner is 4 feet ± South of the centerline of road East and West and 5 feet West of centerline of road going North. Set a 1½" Pipe.

- 28" White Oak N70°E 121.12' #5
- Telephone Pole N65°W 106.73' #6
- Power Pole S70°W 110.06' #7
- Old Fence Post broken off S20°E 26.30' #4

**SURVEY &
REMONUMENTATION**

MAR 1 9 2000

Douglas W. Bonnema R.L.S. #12579

LCRC #344 April 3, 1975 Found 1½" Iron

- 28" Oak East - Northeast 120.68' #5
- 6" Ash East - Southeast 59.25' #9
- Centerline of Street Sign North - Northwest 56.31' #10

SECTION

Norman L. Ochs R.L.S. #22439

LCRC #690 July 15, 1985

Found 1" Pipe and Well Point. Removed and set a 4" x 20" Harrison cast iron monument marked "County Surveyor" and the centerline of road going North is 9 feet East and the centerline of the East and West road is 3 feet North.

- 28" White Oak N65°E 121.00' #5
- Street Sign N25°W 56.15' #10
- Power Pole S60°W 110.00' #7
- Power Pole S65°E 136.98' #11
- Centerline of East and West gravel road is 3 feet North. #12

