

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

FEB 28 PM 1 09

SECTION

Form with fields: For corners in Newaygo (County), Located in: Corner Code #, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

Linda M. Brown

VOL. 2

283

Register of Deeds Stamp & File Number

12x12 grid table with columns A-M and rows 1-13

I, Norman L. Ochs, in a field survey on February 11, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 33, Ensley Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. N. Brookfield 1836 18" Pine N38°W 33 Links (21.78')#1 18" Pine N31½°E 45 Links (29.7')#2

Ralph A. Smith R.L.S. #3421 Book 82, Page 107 January 14, 1960 1½" Iron U.S.G.S. S70½°E 49.3' #3 10" Black Oak N29½°E 30.4' #4 Concrete Fence Post N01°W 30.3' #5 18" Walnut N34½°W 38.7' #6

1909 William & Works Set Iron and small stones.

Newaygo County Road Commission Sheet 1½" Iron U.S.G.S. S70°E 49.3' #3 10" Black Oak N29°E 30.4' #4 Concrete Fence Post N01°W 30.3' #5 18" Walnut N34°W 38.7' #6

OVER ↘

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 4" Harrison cast iron monument marked "County Surveyor". The centerline of the East and West bituminous road is 1.5 feet ± South and there is a tree row going North which starts 800 feet ± North of the corner. The condition of the recorded witnesses are: #1 thru #6 gone, #7 thru #11 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 4" Harrison cast iron monument marked "County Surveyor" as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the original corner.

Northeast Corner, Section 5, Solon Township, Monument with Kent County brass cap, East 110.50' #7 22" Forked Walnut N61°W 84.48' Found spike in Southwesterly side of tree. #8 30" Poplar S09°E 97.95' Set spike with tag #22439 in West side of tree. #9 8" Elm S30°E 62.70' Found spike in Easterly side of tree. #10 Centerline of East and West gravel road North 1.5' ± #11

Signed by Norman L. Ochs Date August 16, 1999 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971 Revised May 14, 1975 Revised Jan., 1983

Approved by Peer Review Group on August 19, 1999 Norman L. Ochs, County Representative.

N.L.O.



A. Description (cont.)

Norman L. Ochs R.L.S. #22439

LCRC #691 July 15, 1985

Found 1½" Iron in centerline of the East and West road and on field line going North. Removed and set a 4" x 20" Harrison cast iron monument marked "County Surveyor"

Northeast Corner, Section 5, Solon Township, East 110.5' #7

28" Walnut N40°W 39.35' #6

20" Forked Walnut N75°W 84.51' #8

12" Poplar S10°E 97.55' #9

5" Elm S55°E 63.58' #10

In centerline of the East and West gravel road #11

Norman L. Ochs R.L.S. #22439

August 4, 1987 Drawing Numbers 87051B thru 87054B

Found 1½" Iron in centerline of 22 Mile road

28" Walnut N40°W 39.35' #6

20" Twin Walnut N75°W 84.51' #8

12" Poplar S10°E 97.55' #9

5" Elm S55°E 63.58' #10

Norman L. Ochs R.L.S. #22439

September 10, 1990 Drawing Number 90213B

Found Concrete Monument

28" Walnut N40°W 39.35' #6

20" Walnut N75°W 84.51' #8

12" Poplar S10°E 97.55' #9

5" Elm S55°E 63.53' #10

SURVEY &
REMONUMENTATION

MAR 1 8 2000

SECTION