

**MAR 1 8 2000**

**1999 Newaygo County Remonumentation Project**

**NEWAYGO COUNTY REGISTER OF DEEDS  
LINDA M. BROWN**

**LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

**00 FEB 28 PM 1 09**

**SECTION**

For corners in  
Newaygo  
(County)

Located in: Corner Code #

*Linda M. Brown*

- 1. Public Land Survey T 11N R 11W I-13  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
- 2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

**VOL. 2 287**

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on August 17, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Southeast Corner, Section 34, Ensley Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

- G.L.O. N. Brookfield 1836  
20" White Oak N04°W 27 Links (17.82')#1  
20" White Oak N60°E 28 Links (18.48')#2
- William M. Jacques (County Surveyor)  
Book B, Page 44 March 28, 1910  
Stone Corner
- Delos G. Anderson (County Surveyor)  
Book A, Pages 349 and 350 July 28 thru 31, 1902  
24" Sugar S55°30'E 58½ Links (38.61')#3
- W & W Information shows corner to be distance West 130.5' from North One Quarter Corner, Section 3, Solon Township
- Glen S. Hackbardt R.L.S. #25844  
June 5, 1988 Job Number 79598  
Found 3" Cast Iron Monument  
24" Cedar N70°E 137.35' #7  
Consumer Power Pole N40°W 136.35' #4
- Norman L. Ochs R.L.S. #22439  
LCRC #693 November 14, 1985  
Found small nail 130.13 feet West of North One Quarter Corner, Section 3, Solon Township, nail is in centerline of the East and West and North roads. Dug for stone. Found stone under nail. Set 4" x 20" Harrison cast iron monument marked "County Surveyor" over stone.
- Power Pole N45°W 136.48' #4  
Street Sign N40°E 57.71' #5  
Telephone Riser N50°W 53.17' #6  
23" Cedar N60°E 137.50' #7  
North One Quarter Corner, Section 3, Solon Township, East 130.13' #8



**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 4" x 12" base of broken Harrison cast iron monument 12" below grade in centerline of gravel road going North and in centerline of the East and West bituminous road. The condition of the recorded witnesses are: #1 thru #3 gone, #4 thru #6 good condition, #7 gone, #8 good condition.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Removed base and set a 4" Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

- Power Pole N32°W 136.49' Found spike with tag #22439 in Southwesterly side of pole. #4
- Centerline of Street Sign Pole N48°E 57.80' #5
- Top center Telephone Riser N25°W 53.27' #6
- North One Quarter Corner, Section 3, Solon Township, Harrison monument with Kent County brass cap, East 130.13' #8

Signed by Norman L. Ochs Date August 17, 1999

Surveyor's Michigan License No. 22439 Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group on August 19, 1999 Revised May 14, 1975  
Norman L. Ochs, County Representative. *M.L.O.* Revised Jan., 1983