

SURVEY & REMONUMENTATION

MAR 1 8 2000

1999 Newaygo County Remonumentation Project
LAND CORNER RECORDATION CERTIFICATE
 FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY REGISTER OF DEEDS
 LINDA M. BROWN

00 FEB 28 PM 1 09

SECTION

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>11W</u>	<u>J-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Linda M. Brown

VOL. 2

288

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on February 11, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

South One Quarter Corner, Section 35, Ensley Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. N. Brookfield 1836
 10" White Oak N14°E 28 Links (18.48') #1
 7" White Oak N22°W 35 Links (23.10') #2

Norman L. Ochs R.L.S. #22439
 LCRC #694 November 23, 1985
 Set Corner by computing half way between the Southeast and Southwest Corners of Section 35. The only known corners. Old fence line is gone and on steep hill side. Set 4" x 20" Harrison cast iron monument marked "County Surveyor" on hillside North of road.
 20" Maple South 51.97' #3
 Clump Elm S85°W 20.56' #4
 24" Twin White Oak N45°E 26.40' #5
 Northeast Corner, Section 3, Solon Township, East 152.22' #6

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 4" Harrison cast iron monument marked "County Surveyor" on line ± with remnants of old fence going North. The centerline of the East and West bituminous road is 24 feet ± South and the Northeast Corner, Section 3, Solon Township is 20.5 feet ± North of the centerline of the East and West bituminous road. The condition of the recorded witnesses are: #1 and #2 gone, #3 dead, #4 thru #6 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 4" Harrison cast iron monument marked "County Surveyor" as a substantial marker for the quarter corner and is accepted as a careful and faithful reestablishment of the original corner.

20" Dead Maple South 51.94' Found spike with tag #22439 in Easterly side of tree. #3
 10" - 10" - 4" Clump Elm S85°W 20.55' Found spike with tag #22439 in South side of tree. #4
 28" Twin White Oak N62°E 26.50' Found spike with tag #22439 in Southeasterly side of tree. #5
 Northeast Corner, Section 3, Solon Township, Monument with Kent County brass cap, East 152.22' #6
 18" Red Oak S20°E 58.31' Set spike with tag #22439 in Southwesterly side of tree.

Signed by Norman L. Ochs Date August 16, 1999

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group on August 19, 1999
 Norman L. Ochs, County Representative.

N.L.O.

