

SURVEY & REMONUMENTATION

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA H. BROWN

SECTION

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

'98 MAR 6 PM 12 34

Linda M. Brown

For corners in Newaygo (County) Located in: _____ Corner Code # _____

1. Public Land Survey T 11N R 11W _____ M-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 2

73

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on September 20, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Southeast Quarter Corner, Section 36, Ensley Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Mullett and Brookfield 1838
 12" Pine S45°W 27 Links (17.82') #1
 13" Pine N05°E 26 Links (17.16') #2

Kent County Road Commission
 Shows distance East 216.6' to North One Quarter Corner, Section 1, T10N R11W, Solon Township.

Newaygo County Road Commission Sheet
 1/2" Iron over 1 3/4" Pipe
 Telephone Pole N80°E 83.7' #3
 Telephone Pole S04°W 21.2' #4

Newaygo Engineering and Survey Company
 LCRC #697 September 27, 1985
 Found 1/2" Pipe in monument box 2 feet North of the centerline of East and West roads and 2 feet East of centerline of road going North. Set a 4" by 20" Harrison County Surveyor monument in monument box.
 "X" in Curb N45°E 34.89' #5
 "X" in Curb N45°W 35.78' #6
 Road Sign N40°W 41.25' #7
 Northwest Corner of Garage S45°E 154.52' #8
 Removed 1/2" Pipe, 1/2" Rod and 3/4" Pipe.

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found 4" diameter Harrison monument in monument box in the centerline of bituminous road going North and the centerline of East and West road is 2 feet South. The condition of the recorded witnesses are: #1 thru #4 gone, #5 thru #8 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Accepted 4" diameter Harrison cast iron monument marked "County Surveyor" in monument box as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

"X" in Curb N45°E 34.95' #5
 "X" in Curb N45°W 35.72' #6
 Road Sign N40°W 41.25' #7
 Northwest Corner of Garage at Foundation S45°E 154.65' #8
 1/2" Rod and Cap #22439 at back of curb (on seam) N45°E 35.20'
 4"-4"-4" Triple Box Elder N13°W 112.20' Set spike and tag in Easterly side of tree.
 8"-8"-8" Triple Box Elder N71°W 125.11' Set spike and tag in South side of tree.

Signed by Norman L. Ochs Date October 10, 1997

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971
 Revised May 14, 1975
 Revised Jan., 1983

Approved by Peer Review Group on October 14, 1997
 Norman L. Ochs, County Representative.

N. L. O.

