

**SURVEY &
REMONUMENTATION**

APR 24 1995 1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

VOL 001 PAGE 76
NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 52

Marlene Toogood

Register of Deeds Stamp & File Number

For corners in

<u>Newaygo</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>12W</u>	<u>D-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Norman L. Ochs, in a field survey on October 13, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

N. 1/4 Corner, Section 8, Grant Twp., Newaygo County, MI

A. Description of original monument and accessories and/or subsequent restoration:	Patrick A. Salisbury R.L.S. #13594
G.L.O. J. H. Mullett 1837	1972 Set 1" Pipe L.C.R.C. #351
12" Pine N52°E 5 lks. (3.3') #1	P. Pole S05°W 130.85' #4
12" Pine S28°W 13 lks. (8.58') #2	14" W. Oak N12°W 63.81' #5
N.C.R.C. Sheet	4" W. Oak S75°E 74.16' #6
Fence Post North 25.60' #3	Doubled line and distance from East and fits
T. Pole S05°W 128.90' #4	occupation. Measured 2649.64 feet from the
	N. 1/4 Cor. to the N.E. Cor. of Sec. 8.

Sometime prior to 1972, The Road Commission cut hill down and the 1/4 Cor. was removed. OVER----->

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On October 13, 1994, I, Norman L. Ochs, found a 1/2" Rod and cap (#30389) and measured 2656.79 feet from the N.W. Cor. to the N. 1/4 Cor. of Sec. 8 and measured 2648.12 feet from the N. 1/4 Cor. to the N.E. Cor. of Sec. 8 and condition of recorded witnesses are: #1 Thru #3 Gone, #4 and #5 Good Condition, #6 Gone, #7 Thru #9 Good Condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1/2" Rod and set a 4" dia. Harrison Cast Iron Monument 20" long stamped County Surveyor as a substantial marker for the original corner and is a careful and faithful reestablishment of the position of the original corner.

- 28" W. Oak N12°W 63.66' Found in East side of tree #5
- P. Pole S05°W 130.25' Spike in West side of pole #4
- P. Pole N25°W 56.14' P.K. Nail in West side of Pole
- 4" Box Elder S70°E 109.07' Spike in N.E. side of tree
- Top Corner Fence Post N67°E 145.75' Found Tag (#30389) on top of post #7
- Top Center Telephone Pedestal S11°E 35.43' #8
- 11" R. Oak N04°W 86.49' Found Tag (#30389) on West side of tree #9



Signed by Norman L. Ochs Date October 25, 1994

Surveyor's Michigan License No. Norman L. Ochs #22439

Approved by Peer Review Group on November 10, 1994
Norman L. Ochs, County Representative. *N.L.O.*

A. Description.....(Continued)

William Fries Jr. R.L.S. #30389 October 18, 1991

Found E. 1/8th Cor. on South Section line and S.E. Cor. as set by Patrick A. Salisbury R.L.S. #13594 in 1972 and doubled that distance to set a 1/2" Rod and Cap for the S. 1/4 Cor.

W. Oak AZ 348° 63.57' #5

Top Cor. Fence Post AZ 67° 145.64' #7

Top Center Tel. Pedestal #1210 AZ 169° 35.44' #8

11"-24" Tw. Oak AZ 356° 86.40' #9