

SURVEY & REMONUMENTATION

1995 Newaygo County Remonumentation Project

APR 04 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY
REG. CLERK
MARLEN T. BOGGS

FEB 21 AM 9 37

Marlene Toogood
VOL. 1 PAGE 157

| | | |
|--|---------------------------|---------------|
| For corners in <u>Newaygo</u> (County) | Located in: | Corner Code # |
| 1. Public Land Survey | T <u>11N</u> R <u>12W</u> | <u>D-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, Norman L. Ochs, in a field survey on November 20, 1995, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

N. ¼ Corner, Section 17, Grant Twp., Newaygo Co., Mi

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

| | |
|--|---|
| G.L.O. J. H. Mullett 1838 10" Tamarack N14°E 38Lks (25.08')#1 12" Tamarack S77°E 35Lks (23.10')#2 | Ralph A. Smith RLS #3421 Book 70 Pg's 152 & 153 1954 Measured 2589.84 ft from the N. ¼ Cor. to the N.E. Cor. of Sec. 17 |
| W.S. Merrill (Co. Surveyor) Book A Pg's 105 & 106 October 3, 1888 Measured 39.24 ch (2589.84 ft) from the N. ¼ Cor. to the N.E. Cor. of Sec. 17 | C.F. Zimmerman P.E. #07301 August 24, 1957 Measured 2639.76 ft from the N.W. Cor. to the N. ¼ Cor. of Sec. 17 Measured 5279.39 ft from the N. ¼ Cor. to the S. ¼ Cor. of Sec. 17 Measured 2589.70 ft from the N. ¼ Cor. to the N.E. Cor. of Sec. 17 |
| NCRC Sheet Measured 2639.76 ft from the N.W. Cor. to the N. ¼ Cor. of Sec. 17 and measured 2589.70 ft from the N. ¼ Cor. to the N.E. Cor. of Sec. 17 | |
| Newaygo Engineering and Survey Co. June 1, 1981 Set ½" Rod by prorated C.F. Zimmerman's distance and bearings. Did not find iron in swamp fill area. 5" Elm N05°E 46.70' #3 12" Maple S45°E 73.85' #4 4" Maple S15°E 57.82' #5 Measured 2639.46 ft from the N.W. Cor. to the N. ¼ Cor. of Sec. 17 and measured 5279.18 ft from the N. ¼ Cor. to the S. ¼ Cor. of Sec. 17 and measured 2593.37 ft from the N. ¼ Cor. to the N.E. Cor. of Sec. 17 | |

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found ½" rod and cap and measured 2639.33 ft from the N.W. Cor. to the N. ¼ Cor. of Sec. 17 and measured 2589.29 ft from the N. ¼ Cor. to the N.E. Cor. of Sec. 17 and the centerline of the E & W road is 0.50 ft North of corner and the condition of the recorded witnesses are: #1 and #2 gone, #3 thru #5 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed ½" rod and cap and set a 4" dia. Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

14" Elm N05°E 46.75' Fnd. spike in East side of tree.#3
14" Maple S45°E 73.85' Set spike in Southwest side of tree. #4
8" Maple S15°E 57.81' Fnd. spike in East side of tree. #5
12" Elm S40°E 45.45' Spike in East side of tree.

Signed by *Norman L. Ochs* Date December 12, 1995
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors Jan 20, 1974
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group On December 13, 1995
Norman L. Ochs, County Representative. *N.L.O.*

