

1994 NEWAYGO COUNTY REMONUMENTATION PROJECT

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Newaygo
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>12W</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VOL **001** PAGE **77**

NEWAYGO COUNTY
REGISTER OF DEEDS
MARLENE TOOGOOD

'95 MAR 14 PM 3 52

Marlene Toogood

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on October 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

NE COR., Sec. 8, Grant Twp., Newaygo County MI

A. Description of original monument and accessories and/or subsequent restoration:

GLO April 25, 1958 Andrew Jackson
 W. Oak 10" S69°W 41 lks (27.06') #1 Drawing No. McD14518-58
 B. Oak 10" S74°E 64 lks (42.24') #2 Measured 2641.82 ft. from the NW cor to the N-1/4 cor. of Sec. 9. Measured 2613.68 ft. from the NW cor. to the W-1/4 cor. of Sec.9.
 Merrill (Co. Surveyor) Book # Unknown
 W. Oak 6" N40°W 40 lks (26.40') #3 C F Zimmerman RPE #7301 July 1964
 P.Stp. S72°E 59-1/2 lks (39.27') #4 Measured 2646.76 ft. from the SW cor. to the S-1/4 cor. of Sec. 4 and measured 2655.10 ft. from the SW cor. to the W-1/4 cor. of Sec. 4.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In October, 1994, I, Norman L. Ochs, found a 1/2" pipe. Replaced with a 4" ^{OVER-} Harrison Cast Iron monument in the exact location. I measured 2648.12 ft. from the N-1/4 cor. to the NE cor. of Section 8 and measured 2611.99 ft. from the NE cor. to the E-1/4 cor. of Section 8.

Condition of recorded witnesses is: #1 thru #4 gone, #5 good condition, #6 and #7 gone, #8 good condition, #9 and #10 gone, #11 thru #13 good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 4" Harrison cast iron monument as a substantial marker for the Section corner and is accepted as a careful and faithful reestablishment of the original corner.
 14" R. Oak S50°E 62.05' Spike on North side of tree #11.
 12"-8" Tw. R. Oak S30°E 70.25' Spike on NE side of tree #12.
 14" Red Oak N45°W 57.38' Spike on South side of tree #13.
 U.S.G.S. monument N44°E 47.54' #5.
 1/2" rod East 32.98' #8.



Signed by Norman L. Ochs Date October 17, 1994
 Surveyor's Michigan License No. 22439

Approved by Peer Review Group on October 19, 1994. FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 Norman L. Ochs, County Representative REVISED MAY 14, 1975
 REVISED JAN., 1983

SURVEY &
REMONUMENTATION

DEC 07 2000

SECTION

A cont.

NCRC Wit. Sheet
3/4" Pipe + 1950's
U.S.G.S. N44°E 47.6' #5
8" Maple N61°E 65.8' #6
12" B. Oak N22°W 47.8' #7

Thomas H. Sage LCRC #1190 11/24/93
1/2" x 24" Galv. Pipe Set
USGS Mon. N44°E 47.6' #5
14" Oak S50°E 62.10' #11
8" Oak S30°E 70.30' #12
14" Oak N45°W 57.31' #13

May 2, 1978 Charles E. Fricke RLS #21781

Iron
Prop. Iron S87°57'E 33.0' #8
Mcg. Co. Standpipe N59°E 66.1' #9
Mcg. Co. Standpipe S75°W 111.0' #10
Recorded in Series J No. 2117
Measured 2645.34 ft. from NW cor.
to N-1/4 cor. of Sec. 9. Measured
2612.30 ft. from NW cor. to W-1/4 cor.
of Sec. 9.

SURVEY &
REMONUMENTATION

DEC 07 2000

SECTION