

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

1996 Newaygo County Remonumentation Project

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

'97 FEB 12 PM 4 45

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 11N R 12W E-11
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 1 PAGE 216

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		6		5		4		3		2		1
5													
6	10		9		8		7		6		5		4
7													
8	19		18		17		16		15		14		13
9													
10	30		29		28		27		26		25		24
11													
12	31		32		33		34		35		36		37
13													

I, Norman L. Ochs, in a field survey on August 31, 1996 do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Northwest Corner, Section 33, Grant Township, Newaygo County, Michigan

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. J.H. Mullett 1838
 12" Beech S49°E 47 Links (31.02') #1
 18" Beech N36°W 20 Links (13.20') #2

Lyle S. Shepherd R.L.S. #503
 Book 70 Page 42 June 5, 1930
 Found Gas pipe in line with fence 33' ± out

William M. Jacques (County Surveyor)
 August 29, 1905 Book 8 Page 69
 Cedar Stake with glass
 40" Pine Stump N11°E 66½ Links (43.89') #3

NCRC Sheet Iron
 24" Oak S68°E 127.2' #4
 8" Apple S21°W 52.9' #5
 Power Pole N02°W 67.3' #6

Newaygo Engineering and Survey Company
 Found ½" Iron June 10, 1978
 14" Red Oak N30°E 45.86' Spike in East side of tree. #7
 Telephone Riser South 30.70' Top centerline #8
 10" Red Oak S39°E 89.40' #9

Duane F. Wood P.S. #24625 LCRC #964
 Found Steel rod in road May 25, 1984
 Twin Oak N25°W 37.90' #10
 20" Oak N25°E 45.85' #7
 Twin Oak South 62.25' #11

OVER ↘

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found ½" Rod 2" below bit inside of 1½" Iron pipe and found remnants of wood stake and the centerline of the East and West road is 2.6 feet South and on line with edge of woods going South and the condition of the recorded witnesses are: #1 thru #3 gone, #4 good condition, #5 gone, #6 good condition, #7 gone, #8 thru #10 good condition, #11 gone, #12 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed ½" Rod and 1½" Iron pipe and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

36" Oak S60°E 128.05' Set spike and tag in Southeasterly side of tree. #4
 Power Pole N04°E 67.68' Set spike and tag in East side of pole. #6
 Telephone Riser South 30.58' #8
 18" Red Oak S40°E 89.40' Found spike in Southwest side of tree. #9
 16"-12" Twin Oak N15°W 37.90' Found spike in Easterly side of tree. #10
 ½" Rod and cap #24625 North 33.00' #12


Signed by Norman L. Ochs Date September 13, 1996

Norman L. Ochs
 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, 1997
 Revised May 14, 1975

Revised Jan., 1983

Approved by Peer Review Group On September 17, 1996
 Norman L. Ochs, County Representative.



M.L.O.

A. Description (cont.)

Newaygo Engineering and Survey Company
Found Steel Bar August 24, 1987
Twin Oak N25°W 37.90' #10
20" Oak N25°E 45.85' #7
Twin Oak South 62.25' #11

Charles E. Fricke P.S. #21781
Survey Recorded in Liber 355 Page 3742
November 17, 1992
Twin Oak N25°W 37.9' #10
20" Oak N25°E 45.8' #7
Twin Oak South 62.2' #11
Property Iron North 33.00' #12