

**SURVEY & REMONUMENTATION**

MAR 13 2000

1999 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS LINDA M. BROWN

LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT of Act 74, Mich. P.A. 1970

00 FEB 28 PM 1 09

**SECTION**

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 11N R 12W G-13  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_

2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Linda M. Brown*

VOL. 2

298

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on February 17, 1999, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Southeast Corner, Section 33, Grant Township, Newaygo County, Michigan.

**A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:**

G.L.O. N. Brookfield 1836  
 10" Birch N61°E 10 Links (6.60') #1  
 12" Hemlock N44°W 27 Links (17.82') #2

Lyle S. Shepherd R.L.S. #503  
 June 5, 1930 Book 70, Page 42  
 Gas Pipe in centerline of gravel.  
 Measured 2668 feet from the Southeast Corner to the South One Quarter Corner of Section 33, T11N R12W.

William M. Jacques (County Surveyor)  
 Book 8, Pages 33 and 34 August 19 and 20, 1913  
 Iron Measured 40 Chains 48 feet (2688') from the Southwest Corner to the South One Quarter Corner of Section 34, T11N R12W.

Newaygo County Road Commission Sheet  
 1/2" Iron  
 6" Willow S50°E 31.6' #3  
 12" Elm S14°W 21.25' #4  
 Telephone Pole S73°W 100.2' #5

Norman L. Ochs R.L.S. #22439  
 February 23, 1983 Drawing Number 83020B  
 Found 5/8" Rod  
 Telephone Riser S50°W 66.75' #6  
 8" Ash S15°E 49.34' #7

OVER ↵

**B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:**

Found 4" Harrison cast iron monument marked "County Surveyor" in the centerline of bituminous road going North and the centerline of the East and West bituminous road is 2 feet ± North. The condition of the recorded witnesses are: #1 thru #5 gone, #6 good condition, #7 thru #10 gone.

**C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:**

Accepted 4" Harrison cast iron monument marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Telephone Riser S60°W 66.97' to top centerline. #6  
 Power Pole N15°E 183.55' Found spike in West side of pole.  
 Street Sign N45°E 64.83' to centerline of pole.  
 Stop Sign N37°W 64.40' to centerline of East leg.

Signed by Norman L. Ochs Date August 16, 1999  
 Norman L. Ochs  
 Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 23, 1975



Approved by Peer Review Group on August 19, 1999  
 Norman L. Ochs, County Representative.

*N.L.O.*

A. Description (cont.)

Norman L. Ochs R.L.S. #22439

LCRC #681 September 11, 1985

Found 5/8" Rod. Removed and set a 4" X 20" Harrison cast iron monument marked "County Surveyor".

4" - 10" Twin Ash S15°E 49.28' #7

8" Clump of Elms N15°E 156.55' #8

Street Sign N45°E 48.9' #9

Stop Sign N45°W 43.42' #10

SURVEY &  
REMONUMENTATION

MAR 1 3 2000

SECTION