

**SURVEY &
REMONUMENTATION**

MAR 19 1998

1997 Newaygo County Remonumentation Project

NEWAYGO COUNTY
REGISTER OF DEEDS
LINDA M. BROWN

SECTION

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'98 MAR 6 PM 12:34

Linda M. Brown

For corners in <u>Newaygo</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>12W</u> T <u>12N</u> R <u>12W</u> T _____ R _____ T _____ R _____	<u>L-1</u> ✓ <u>L-13</u> _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

VOL. 2

69

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman L. Ochs, in a field survey on July 8, 1997, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Note: This Corner is common to both sections.
North One Quarter Corner, Section 1, Grant Township, Newaygo County, Michigan
South One Quarter Corner, Section 36, Brooks Township, Newaygo County, Michigan

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. Brookfield and Hodgson 1838
7" Maple N25°W 7 Links (4.62') #1
8" Maple N43°E 13 Links (8.58') #2

Ralph A. Smith R.L.S. #3421
Book 70 Page 1 thru 3 June 30, 1959
Set ¾" Pipe half-way between corners
8" Black Oak S20°W 24.8' #4
8" Twin Oak S65°E 57.0' #5
10" Black Oak N15°W 67.7' #6

William M. Jacques (County Surveyor)
Book 14 Page 24 April 21, 1904
24" Pine Stump S27°W 51' #3

Robert Wetherell R.L.S. #24624
April 3, 1978 File Number 3010-78
14" Black Oak S20°W 24.8' (old bearing tree) #4
12" Oak S65°E 57.0' (old bearing tree) #5
14" Black Oak N15°W 67.7' (old bearing tree) #6

Newaygo Engineering and Survey Company
1984 ¾" Pipe
14" Black Oak S20°W 24.8' #4
12" Twin Oak S65°E 57.0' #5
10" Black Oak N15°W 68.22' #6

OVER ↘

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Found ¾" X 20" Iron pipe in centerline of East and West gravel road and on West edge of pine plantation going North and the condition of the recorded witnesses are: #1 and #2 gone, #3 remains of stump, #4 thru #7 good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Removed ¾" X 20" Iron pipe and set a 4" diameter Harrison cast iron monument 20" long marked "County Surveyor" as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

28" Black Oak S21°W 24.8' Found spike in East side of tree. #4
24"-24" Twin Black Oak S56°E 57.0' Set spike with tag in Southwest side of tree. #5
22" Black Oak N06°W 68.25' Found spike in East side of tree. #6
16"-14" Black Oak N01°E 106.94' Found nail in root in Southeast side of tree. #7

Signed by Norman L. Ochs Date September 8, 1997

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors on Jan 23, 1971

Approved by Peer Review Group on September 9, 1997

Norman L. Ochs, County Representative.

N.L.O.

