

1993

1993 NEWAYGO COUNTY REMONUMENTATION PROJECT: NEWAYGO COUNTY

REGISTER OF DEEDS  
MARLENE TOOGOOD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

94 JAN 21 PM 3 24

For corners in

NEWAYGO  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 11N R 13W A-1
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Marlene Toogood*

VOL 001 PAGE 03

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Norman L. Ochs, in a field survey on December 5, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**  
NW Corner, Section 6, Ashland Twp.

A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O. J. Mullett 1837 April 16, 1959  
 12" Beech N81°W 23 lks (15.18') #1 Ralph A. Smith #3421  
 14" Beech S51°W 38 lks (25.08') #2 Field Book 84A Pg. 25  
 Fd. 1-1/2" pipe with broken glass & crockery  
 1903 William M. Jacques 8" Elm N75°+E 75.2' #3  
 Book A pg. 369 6" Elm N60°+W 57.4' #4  
 Fnd. good cor. post that was set by W. S. Merrill & one CL Ditch North 25' #5  
 O.B.T. stumps CL Ditch West 11' #6

NCRC Sheet Iron  
 P Pole N88°W 77.7'  
 30" Maple S13°E 78.6' #8  
 1978 Clinton E. Cole #17615  
 5" Sass. N58°W 29.35' #9  
 4" Poplar N62°E 23.57' #10  
 8" Oak S37°E 36.64' #11

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 In 1893 W. S. Merrill surveyed Section 1 of Bridgeton Twp. and set a post for corner, left no witnesses. See book A, Pg. 131 & 132.  
 In 1903 Wm. Jacques surveyed Sec. 31, of Garfield Twp., and found "a good corner post set by W.S. Merrill" and left no witnesses. See Book #1, Pg. 24 & 25 "Register of Deeds."  
 In 1959 R. A. Smith, RLS #3421 surveyed Sec. 6, of Ashland Twp. He found a 1-1/2" pipe with broken crockery and glass. See F Book, 84A pg. 25.  
 In 1993 N.E. & S found 1-1/2" pipe, glass & crockery. Condition of recorded witnesses is 1 thru 4 and 7 and 8 are gone, 5 and 6 fit good, 9 and 10 good condition  
 I feel that the crockery & glass are left from the 1903 survey by Wm. Jacques.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Accepted 4" Harrison cast iron monument as a substantial marker for the Section corner and is accepted as a careful and faithful reestablishment of the original corner  
 5" Sass N57°W 30.15' Spike in North side of tree #9.  
 12" W. Oak S37°E 36.57' Spike in North side of tree #11  
 3" R. Pine S40°W 57.07' Spike in Northerly side of the tree.  
 1/2" rod (Burt Wickham's cor) S03°W 33.07'. (RLS #17639)  
 5" Maple S55°E 29.73' Spike in South side of tree.



Signed by *Norman L. Ochs*  
 Norman L. Ochs  
 22439

Date December 20, 1993

Surveyor's Michigan License No. \_\_\_\_\_  
 Approved by Peer Review Group Dec. 21, 1993  
 Norman L. Ochs, County Representative