

SURVEY & REMONUMENTATION

MAR 02 1999

1998 Newaygo County Remonumentation Project

NEWAYGO COUNTY REGISTER OF DEEDS
LINDA M. BROWN

SECTION

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT of Act 74, Mich. P.A. 1970**

'99 FEB 17 PM 3 33

Linda M. Brown

For corners in Newaygo (County) Located in: Corner Code #

1. Public Land Survey T 11N R 13W E-10
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

VOL. 2

160

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman L. Ochs, in a field survey on October 29, 1998, do hereby certify that under requirements of P. A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

West One Quarter Corner, Section 28, Ashland Township, Newaygo County, Michigan.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

G.L.O. James H. Mullett 1838
24" Beech N55°E 46 Links (30.36') #1
6" Beech S45°W 4 Links (2.64') #2

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

Dug and searched for any previous evidence and found nothing. Set on line and at a point of intersection of remnants of the East and West fence and remnants of the North and South fence. The condition of the recorded witnesses are: #1 and #2 gone.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

Set a 4" diameter Harrison cast iron monument 16" long marked "County Surveyor" and built a stone pile around it as a substantial marker for the section corner and is accepted as a careful and faithful reestablishment of the original corner.

Maple (blazed) N22°E 24.37' Set spike with tag #22439 in Southeasterly side of tree.
12" Red Oak (blazed) S75°W 23.51' Set spike with tag #22439 in North side of tree.
8" Red Pine N53°W 42.97' Set spike with tag #22439 in Southerly side of tree.
20" Maple (blazed) S40°E 2.61' Set spike with tag #22439 in Northeasterly side of tree.

Signed by Norman L. Ochs Date December 19, 1998
Norman L. Ochs

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan 28, 1971

Approved by Peer Review Group On December 22, 1998
Norman L. Ochs, County Representative.

Revised May 14, 1975

Revised Jan., 1983

N.L.O.

